

AD-A053 610

BELL AEROSPACE TEXTRON BUFFALO N Y
LACV-30 TEST AND DEMONSTRATION REPORT.(U)
FEB 78 M M LASZEWSKI
7467-928009

F/G 1/3

UNCLASSIFIED

DAAK02-75-C-0149
NL

1 OF 2
ADA
053810



AD A 053610

AD No.

DDC FILE COPY

REPORT: 7467-928009

LACV-30 TEST AND DEMONSTRATION REPORT

Marion M. Laszewski
Bell Aerospace Textron
P. O. Box 1
Buffalo, New York 14240


FEBRUARY 1978

FINAL REPORT

Approved for Public Release; Distribution
is unlimited

PREPARED FOR

U.S. ARMY MOBILITY EQUIPMENT RESEARCH AND DEVELOPMENT
COMMAND
Ft. Belvoir, VA



REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) LACV-30 TEST AND DEMONSTRATION REPORT.		5. TYPE OF REPORT & PERIOD COVERED Final Report
6. PERFORMING ORG. REPORT NUMBER 7467-9280091		7. CONTRACT OR GRANT NUMBER(s) DAAK02-75-C-0149
8. AUTHOR(s) Marion M./Laszewski		9. PERFORMING ORGANIZATION NAME AND ADDRESS Bell Aerospace Textron P. O. Box 1 Buffalo, New York 14240
10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS 12 160p		11. CONTROLLING OFFICE NAME AND ADDRESS U. S. Army Mobility Equipment Research and Development Command Ft. Belvoir, VA
12. REPORT DATE Feb 1978		13. NUMBER OF PAGES 159
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report) Unclassified
15a. DECLASSIFICATION/DOWNGRADING SCHEDULE		
16. DISTRIBUTION STATEMENT (of this Report) <div style="border: 1px solid black; padding: 5px; text-align: center;">DISTRIBUTION STATEMENT A Approved for public release; Distribution Unlimited</div>		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report) Approved for Public Release; Distribution is unlimited		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) U. S. Army Logistic Air Cushion Vehicle		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report presents the test data and analysis of all acceptance and type tests performed on the LACV-30-1 and -2 vehicles. The tests were performed as specified in Contract No. DAAK02-75-C-0149 dated 7 March 1975. All test data were accepted by the U.S. Army prior to delivery of the vehicles. Two corrective actions were required on the LACV-30-1, installation of a new horn and addition of bow pre-loaders to maintain pressure on the front landing pads during swing crane operation.		

ABSTRACT

This report presents the test data and analysis of all acceptance and type tests performed on the LACV-30-1 and LACV-30-2 vehicles. The tests were performed as specified in Contract No. DAAK02-75-C-0149 dated 7 March 1975.

All test data were accepted by the U. S. Army prior to delivery of the vehicles. Two corrective actions were required on the LACV-30-1, installation of a new horn and addition of bow pre-loaders to maintain pressure on the front landing pads during swing crane operation.

ACCESSION for
NTIS White Section ☒
DOC Blue Section ☐
NAVJAG ☐
U.S. AIR FORCE
BY
CONFIDENTIALITY CODES
CONFIDENTIAL

TABLE OF CONTENTS

	<u>PAGE</u>
1.0 INTRODUCTION	1
1.1 GENERAL	1
1.2 GENERAL VEHICLE DESCRIPTION	1
1.2.1 GENERAL	1
1.2.2 VEHICLE CHARACTERISTICS	3
1.2.2.1 PRINCIPAL DIMENSIONS	3
1.2.2.2 POWER & TRANSMISSION	3
1.2.2.3 FUEL	4
1.2.2.4 ELECTRICAL	4
1.2.3 INSTRUMENTATION SYSTEM	4
2.0 APPLICABLE DOCUMENTS	9
3.0 TEST PLAN	10
4.0 TEST DATA AND ANALYSIS	14
4.1 TEST DATA	14
4.2 ANALYSIS	14
4.2.1 ACCEPTANCE TESTS	14
4.2.1.1 HOVER TESTS	14
4.2.1.2 SPEED RUNS	14
4.2.1.3 SWING CRANE TEST	15
4.2.1.4 SYSTEM RUN-IN TEST	15
4.2.2 TYPE TESTS	15
4.2.2.1 CABIN NOISE LEVEL	16
4.2.2.2 MANEUVERING	17
4.2.2.3 OBSTACLE TESTS	17
4.2.2.4 SAFE LIMITS	17
4.2.2.5 ENGINE FAILURE - "CRASH STOP"	18
4.2.2.6 ENGINE FAILURE "SPIN OUT"	18
4.2.2.7 THRUST LOADING	18
4.2.2.8 AIR CONDITIONING	19
4.2.2.9 PROPELLER REVERSAL	19
4.2.2.10 CABIN CONTAMINATION	19
4.2.2.11 SKIRT PRESSURE SURVEY	19
APPENDIX A CONTRACTORS' ACCEPTANCE TESTS	A-1
APPENDIX B 1976 IR&D REPORT 7467-928002 "COMPARISON OF MEASURED AND PREDICTED HOVER PERFORMANCE OF LACV-30 VEHICLES AT BATNFO" 31 DECEMBER 1976	B-1

LIST OF FIGURES

FIGURE		PAGE
1.1	3 VIEW AND GENERAL ARRANGEMENT - LACV-30	8
4.1	LACV-30-1 ACCEPTANCE TEST - SPEED RUN OVER WATER	84
4.2	LACV-30-2 ACCEPTANCE TEST - SPEED RUN OVER WATER	85
4.3	LACV-30-1 TURNING RADIUS OVER WATER	86
4.4	LACV-30-1 TURNING RADIUS OVER WATER	87

LIST OF TABLES

TABLE		
1.1	INSTRUMENTATION PACKAGE ON LACV-30-2	6
3.1	TYPE AND ACCEPTANCE TESTS (OVER LAND)	11
3.2	TYPE AND ACCEPTANCE TESTS (OVER WATER)	12
3.3	COMPLETED TYPE AND ACCEPTANCE TESTS	13
4.1	LACV-30-1 TESTS AT BAT	20
4.2	LACV-30-1 TESTS AT FT. STORY	42
4.3	LACV-30-2 AT BAT	58
4.4	LACV-30-2 AT APG	68
4.5	THRUST LOADING	83

1.0 INTRODUCTION

1.1 GENERAL

This Test and Demonstration Report for the LACV-30 Air Cushion Vehicle fulfills the requirement of Contract No. DAAK02-75-C-0149. This report includes all the acceptance and type tests performed on the LACV-30-1 and LACV-30-2 vehicles as part of the vehicle demonstration program and proof of design tests.

Where possible, vehicle performance estimates are presented for comparison to measured test data. Contractor's tests performed but not specified in the contract are presented in the Appendices.

1.2 GENERAL VEHICLE DESCRIPTION

1.2.1 GENERAL

The Bell Model 7467 LACV-30 (Lighter, Amphibian Air Cushion Vehicle-30-Ton Payload) is a fully amphibious, high speed craft planned to meet projected Army needs as identified in the Required Operational Capability Document (ROC). It is a high mobility vehicle capable of transporting military cargo payloads in the 25 to 30 short ton category (including MILVANS) primarily in support of the logistics over-the-shore (LOTS) mission involving operations over water, marginal areas and land.

The LACV-30 is a hardened version of the standard commercial Bell "Voyageur" Model 7380 ACV which is in production and already operating in a number of remote area cargo haul applications.

To provide the U. S. Army with an optimum craft, the following hardening items are included in the LACV-30:

<u>Hardening Item</u>	<u>Provides</u>
1. Longitudinal Stretch	Increased payload weight and deck area capability
2. Air Management System	Longer engine life (intake air filtration to remove sand/water). Improved quality air to cabin. More lift fan output for cushion air. APU power take-off availability provides 15 VAC. High intake stack minimizes water ingestion in the surf zone.

<u>Hardening Item</u>	<u>Provides</u>
3. Load-Spreader Pallets	Loading of U. S. Army-specified tracked and wheeled vehicles and containers.
4. Surf Fence	Improved surf transition.
5. Up-rated Engines	Increased payload and/or craft performance.
6. Improved Propeller Blades	Increased payload and/or craft performance.
7. Communications/Navigation System	Compatibility with U. S. Army requirements. Night and low visibility operations.
8. Cabin Sound-proofing	Improved habitability for intensive operations.
9. Cargo Securing System	Fast, effective cargo tie-down System
10. Anchor System	Craft anchoring
11. Cabin Air Conditioning	Heating and cooling for improved habitability
12. Deck Winch	Cargo handling. Craft self-retrieval and improved gradeability.
13. Auxiliary Equipment	To Army requirements
14. Craft Marking	To Army requirements
15. Bow Ramp System (Ground Support Equipment)	Roll-on/roll-off of specified tracked and wheeled Army vehicles and MHE
16. Craft Fendering (Ground Support Equipment)	Improved craft skirt protection during operations alongside container ships
17. Swing Crane	Self-unloading capability

1.2.2 VEHICLE CHARACTERISTICS

A 3-view of the Model 7467 LACV-30 is provided in Figure 1.1. The following subsections give leading particulars of the vehicle.

1.2.2.1 PRINCIPAL DIMENSIONS

Overall length (without optional swing crane)	76 ft 3 in
Overall beam (skirts inflated)	36 ft 8 in
Overall height on landing pads	21 ft 6 in
Overall height from skirt hemlines (hovering)	24 ft 8 in
Cargo deck length	51 ft 6 in
Cargo deck width	32 ft 6 in
Cargo deck height	3 ft 11.5 in
Cushion Height	4 ft 0 in
Cushion area	2061 sq ft
Cushion pressure at gross weight 1g	55.8 psf
Reserve buoyancy	155%

1.2.2.2 POWER AND TRANSMISSION

Engines	2 UACL/Pratt & Whitney Twin Pac ST6T-76 gas turbines
Maximum rating (std day) (each)	1850 SHP
Normal rating (std day) (each)	1400 SHP
Propellers	Two Hamilton Standard 3-blade variable pitch (HSD Model 43D50-363)
Lift Fan	Two Bell/British Hover- craft Corp., 7 ft. centrifugal, 12-bladed, fixed pitch

1.2.2.3

FUEL

Fuel Types	Standard turbine fuel either Jet A-1, JP-4, JP-5, or light diesel fuel oil
Main fuel usable capacity	1,272 U.S. Gal. (15,450 lb)
Fuel Ballast Emergency fuel capacity	294 U.S. Gal. (5,400 lb)

1.2.2.4

ELECTRICAL

Starter Generators per Twin Pac

Powerplant	Two (4 total) Gearbox driven brushless 28 VDC, 200 amps (each)
Batteries	Two nickel-cadmium 28 VDC, 40 amp hr (each)
Generator (APU)	One gearbox driven 115 VAC, 400 H.

1.2.3

INSTRUMENTATION SYSTEM

The U. S. Army follow-on Development Test Program for LACV-30-2 employed an analog instrumentation system capable of recording 76 multiplexed channels of data on magnetic tape. The data were capable of being time-coded, voice-annotated, and event-marked.

The major portion of this data acquisition system is pallet mounted and installed on the fore deck just below the cabin. The pallet contains the tape recorder, multiplexes, signal conditioners, amplifiers, converters, patch panel, time code generator, power distribution panel, and attitude/rate gyros. The system controls and displays (time, oscillograph, and visual meters) are located in the cabin and manned by the navigator. Primary power (28 vdc and 115v 400H AC) is supplied from the craft electrical system to the pallet and distributed. Table 1.1 is a listing of parameters with range and type of sensor to be used.

Data were gathered in land and water tests as required by specific development test objectives. All parameters are recorded. The patch panel is utilized to provide the test engineer with selected

information pertinent to a particular test. These data can be "quick look" reviewed to verify attaining test conditions and to determine trend information.

The test engineer is provided with an "Event Mark" control to identify a specific data point on all recorded information. Additionally, the test engineer maintains a detailed log in time code of all tests and significant occurrences.

The Instrumentation System was installed by BAT and its operation verified during the Contractor Test Program.

TABLE 1.1. INSTRUMENTATION PACKAGE ON LACV-30-2

<u>PARAMETER</u>	<u>RANGE</u>	<u>SENSOR</u>	<u>ERROR</u>
1. Power Turbine Temperature	0-1300°F	Engine Pickup	±10°
2. Power Turbine Temperature	0-1300°F	Engine Pickup	±10°
3. Power Turbine Temperature	0-1300°F	Engine Pickup	±10°
4. Power Turbine Temperature	0-1300°F	Engine Pickup	±10°
5. Gas Generator RPM	0-105%	Engine Pickup	±.5%
6. Gas Generator RPM	0-105%	Engine Pickup	±.5%
7. Gas Generator RPM	0-105%	Engine Pickup	±.5%
8. Gas Generator RPM	0-105%	Engine Pickup	±.5%
9. Power Turbine RPM	0-100%	Engine Pickup	±.5%
10. Power Turbine RPM	0-100%	Engine Pickup	±.5%
11. Power Turbine RPM	0-100%	Engine Pickup	±.5%
12. Power Turbine RPM	0-100%	Engine Pickup	±.5%
13. Engine Torque	0-70 psi	Engine Pickup	±1.0 psi
14. Engine Torque	0-70 psi	Engine Pickup	±1.0 psi
15. Engine Torque	0-70 psi	Engine Pickup	±1.0 psi
16. Engine Torque	0-70 psi	Engine Pickup	±1.0 psi
17. Air Intake Temperature	-70 +200°F	IC Couple	±4°F
18. Air Intake Temperature	-70 +200°F	IC Couple	±4°F
19. Air Intake Temperature	-70 +200°F	IC Couple	±4°F
20. Air Intake Temperature	-70 +200°F	IC Couple	±4°F
21. Engine Bay Temperature	0-400°F	IC Couple	±4°F
22. Engine Bay Temperature	0-400°F	IC Couple	±4°F
23. Engine Bay Temperature	0-400°F	IC Couple	±4°F
24. Engine Bay Temperature	0-400°F	IC Couple	±4°F
25. Engine Bay Temperature	0-400°F	IC Couple	±4°F
26. Engine Bay Temperature	0-400°F	IC Couple	±4°F
27. Engine Bay Temperature	0-400°F	IC Couple	±4°F
28. Engine Bay Temperature	0-400°F	IC Couple	±4°F
29. Engine Bay Temperature	0-400°F	IC Couple	±4°F
30. Fuel Flow	0-5 GPM	Potter	±.025 GPM
31. Fuel Flow	0-5 GPM	Potter	±.025 GPM
32. Fuel Flow	0-5 GPM	Potter	±.025 GPM
33. Fuel Flow	0-5 GPM	Potter	±.025 GPM
34. Propeller Blade Angle	±25°	Potentiometer	±.5°
35. Propeller Blade Angle	±25°	Potentiometer	±.5°
36. Forward Trunk Pressure	0-100 psf	Press. Xducer	±.7 psf
37. Forward Trunk Pressure	0-100 psf	Press. Xducer	±.7 psf
38. Rear Trunk Pressure	0-120 psf	Press. Xducer	±.84 psf
39. Peripheral Trunk Pressure	0-100 psf	Press. Xducer	±.7 psf
40. Peripheral Trunk Pressure	0-100 psf	Press. Xducer	±.7 psf
41. Keel Trunk Pressure	0-100 psf	Press. Xducer	±.7 psf
42. Stab. Trunk Pressure	0-100 psf	Press. Xducer	±.7 psf
43. Stab. Trunk Pressure	0-100 psf	Press. Xducer	±.7 psf
44. Rear Trunk Pressure	0-120 psf	Press. Xducer	±.84 psf
45. Cushion Pressure	0-75 psf	Press. Xducer	±.5 psf
46. Cushion Pressure	0-75 psf	Press. Xducer	±.5 psf
47. Cushion Pressure	0-75 psf	Press. Xducer	±.5 psf
48. Cushion Pressure	0-75 psf	Press. Xducer	±.5 psf
49. Pitch Attitude	±60°	Gyro	±.5°
50. Roll Attitude	±60°	Gyro	±.5°
51. Roll Rate	±60°/sec	Gyro	±.6 - 1.2°/sec
52. Pitch Rate	±60°/sec	Gyro	±.6 - 1.2°/sec
53. Yaw Rate	±60°/sec	Gyro	±.6 - 1.2°/sec
54. C.G. Acceleration Vertical	±5g	Accelerometer	±.04g

TABLE 1.1 (Cont'd)

<u>PARAMETER</u>	<u>RANGE</u>	<u>SENSOR</u>	<u>ERROR</u>
55. C.G. Acceleration Long.	±5g	Accelerometer	±.04g
56. C.G. Acceleration Lateral	±5g	Accelerometer	±.04g
57. Bow Acceleration Vertical	±10g	Accelerometer	±.075g
58. Air Management Pressure	0-.5 psi	Press. Xducer	±.0035 psi
59. Air Management Pressure	0-.5 psi	Press. Xducer	±.0035 psi
60. Air Management Pressure	0-.5 psi	Press. Xducer	±.0035 psi
61. Air Management Pressure	0-.5 psi	Press. Xducer	±.0035 psi
62. Air Management Pressure	0-.5 psi	Press. Xducer	±.0035 psi
63. Air Management Pressure	0-.5 psi	Press. Xducer	±.0035 psi
64. Air Speed	0-100 MPH	Anemometer	±1 MPH
65. Wind Direction	±170°	Vane	±2.0°
66. Puff Port L	ON/OFF	Switch	---
67. Puff Port R	ON/OFF	Switch	---
68. Air Management Temperature	0-250°F	IC Couple	±4°F
69. Air Management Temperature	0-250°F	IC Couple	±4°F
70. Strut Load Port L/H	15K psi	Strain Gage	±.3K psi
71. Strut Load Port R/H	15K psi	Strain Gage	±.3K psi
72. Strut Load Stbd. L/H	15K psi	Strain Gage	±.3K psi
73. Strut Load Stbd. R/H	15K psi	Strain Gage	±.3K psi
74. Time Code	----	----	---
75. Intercom	----	----	---
76. Event Marker	----	----	---

DATA
 1. 0017 Class/Type: Joint Chief Communications - LACV-30
 2. 0018 Class/Type: Joint Chief Communications - LACV-30
 3. 0019 Class/Type: Joint Chief Communications - LACV-30
 4. 0020 Class/Type: Joint Chief Communications - LACV-30
 5. 0021 Class/Type: Joint Chief Communications - LACV-30
 6. 0022 Class/Type: Joint Chief Communications - LACV-30
 7. 0023 Class/Type: Joint Chief Communications - LACV-30
 8. 0024 Class/Type: Joint Chief Communications - LACV-30
 9. 0025 Class/Type: Joint Chief Communications - LACV-30
 10. 0026 Class/Type: Joint Chief Communications - LACV-30
 11. 0027 Class/Type: Joint Chief Communications - LACV-30
 12. 0028 Class/Type: Joint Chief Communications - LACV-30
 13. 0029 Class/Type: Joint Chief Communications - LACV-30
 14. 0030 Class/Type: Joint Chief Communications - LACV-30
 15. 0031 Class/Type: Joint Chief Communications - LACV-30
 16. 0032 Class/Type: Joint Chief Communications - LACV-30
 17. 0033 Class/Type: Joint Chief Communications - LACV-30
 18. 0034 Class/Type: Joint Chief Communications - LACV-30
 19. 0035 Class/Type: Joint Chief Communications - LACV-30
 20. 0036 Class/Type: Joint Chief Communications - LACV-30
 21. 0037 Class/Type: Joint Chief Communications - LACV-30
 22. 0038 Class/Type: Joint Chief Communications - LACV-30
 23. 0039 Class/Type: Joint Chief Communications - LACV-30
 24. 0040 Class/Type: Joint Chief Communications - LACV-30
 25. 0041 Class/Type: Joint Chief Communications - LACV-30
 26. 0042 Class/Type: Joint Chief Communications - LACV-30
 27. 0043 Class/Type: Joint Chief Communications - LACV-30
 28. 0044 Class/Type: Joint Chief Communications - LACV-30
 29. 0045 Class/Type: Joint Chief Communications - LACV-30
 30. 0046 Class/Type: Joint Chief Communications - LACV-30
 31. 0047 Class/Type: Joint Chief Communications - LACV-30
 32. 0048 Class/Type: Joint Chief Communications - LACV-30
 33. 0049 Class/Type: Joint Chief Communications - LACV-30
 34. 0050 Class/Type: Joint Chief Communications - LACV-30
 35. 0051 Class/Type: Joint Chief Communications - LACV-30
 36. 0052 Class/Type: Joint Chief Communications - LACV-30
 37. 0053 Class/Type: Joint Chief Communications - LACV-30
 38. 0054 Class/Type: Joint Chief Communications - LACV-30
 39. 0055 Class/Type: Joint Chief Communications - LACV-30
 40. 0056 Class/Type: Joint Chief Communications - LACV-30
 41. 0057 Class/Type: Joint Chief Communications - LACV-30
 42. 0058 Class/Type: Joint Chief Communications - LACV-30
 43. 0059 Class/Type: Joint Chief Communications - LACV-30
 44. 0060 Class/Type: Joint Chief Communications - LACV-30
 45. 0061 Class/Type: Joint Chief Communications - LACV-30
 46. 0062 Class/Type: Joint Chief Communications - LACV-30
 47. 0063 Class/Type: Joint Chief Communications - LACV-30
 48. 0064 Class/Type: Joint Chief Communications - LACV-30
 49. 0065 Class/Type: Joint Chief Communications - LACV-30
 50. 0066 Class/Type: Joint Chief Communications - LACV-30
 51. 0067 Class/Type: Joint Chief Communications - LACV-30
 52. 0068 Class/Type: Joint Chief Communications - LACV-30
 53. 0069 Class/Type: Joint Chief Communications - LACV-30
 54. 0070 Class/Type: Joint Chief Communications - LACV-30
 55. 0071 Class/Type: Joint Chief Communications - LACV-30
 56. 0072 Class/Type: Joint Chief Communications - LACV-30
 57. 0073 Class/Type: Joint Chief Communications - LACV-30
 58. 0074 Class/Type: Joint Chief Communications - LACV-30
 59. 0075 Class/Type: Joint Chief Communications - LACV-30
 60. 0076 Class/Type: Joint Chief Communications - LACV-30
 61. 0077 Class/Type: Joint Chief Communications - LACV-30
 62. 0078 Class/Type: Joint Chief Communications - LACV-30
 63. 0079 Class/Type: Joint Chief Communications - LACV-30
 64. 0080 Class/Type: Joint Chief Communications - LACV-30
 65. 0081 Class/Type: Joint Chief Communications - LACV-30
 66. 0082 Class/Type: Joint Chief Communications - LACV-30
 67. 0083 Class/Type: Joint Chief Communications - LACV-30
 68. 0084 Class/Type: Joint Chief Communications - LACV-30
 69. 0085 Class/Type: Joint Chief Communications - LACV-30
 70. 0086 Class/Type: Joint Chief Communications - LACV-30
 71. 0087 Class/Type: Joint Chief Communications - LACV-30
 72. 0088 Class/Type: Joint Chief Communications - LACV-30
 73. 0089 Class/Type: Joint Chief Communications - LACV-30
 74. 0090 Class/Type: Joint Chief Communications - LACV-30
 75. 0091 Class/Type: Joint Chief Communications - LACV-30
 76. 0092 Class/Type: Joint Chief Communications - LACV-30
 77. 0093 Class/Type: Joint Chief Communications - LACV-30
 78. 0094 Class/Type: Joint Chief Communications - LACV-30
 79. 0095 Class/Type: Joint Chief Communications - LACV-30
 80. 0096 Class/Type: Joint Chief Communications - LACV-30
 81. 0097 Class/Type: Joint Chief Communications - LACV-30
 82. 0098 Class/Type: Joint Chief Communications - LACV-30
 83. 0099 Class/Type: Joint Chief Communications - LACV-30
 90. 0100 Class/Type: Joint Chief Communications - LACV-30




FIGURE 1.1. 3 VIEW AND GENERAL ARRANGEMENT - LACV-30

2.0

APPLICABLE DOCUMENTS

The specifications and documents listed below are the basis for the LACV-30 Test Program and vehicle performance.

(a) Contract No. DAAK-2-75-C-0149, U. S. Army Mobility Equipment Research and Development Center, Ft. Belvoir, Virginia, 7 March 1975.

(b) United Aircraft of Canada Limited, "Installation Manual ST6T-76 Twinned Turboshift Engine."

(c) Pratt and Whitney Aircraft of Canada Ltd., ST6T-76 Twin Turboshift Engine - Specific Operating Instructions," Part No. 3028241, 27 October 1975.

(d) Hamilton Standard "Model Specification for 43D50-359 Controllable Pitch Propeller Assembly," Model Specification No. MS 5088.

(e) Hamilton Standard "Model Specification for 43D50-363 Controllable Pitch Propeller Assembly," Model Specification No. 5122.

(f) Bell Aerospace Company "Technical Proposal for LACV-30-2 Instrumentation System (TECOM) Report No. 7467-953007, June 1975.

(g) Bell Aerospace Company "Calibration Requirements Summary LACV-30-2, Contract DAAK02-75-C-0149 Mod P00003 Data Item C001" Report No. 7467-956008, March 1976.

(h) Bell Aerospace Textron, "LACV-30 Pre-Delivery Water Test Program," Report No. 7467-958006, February 1978.

(i) Bell Aerospace Textron "U.S. Army Lighter ACV LACV-30 P/N 4-099001-1, Operating Manual," Report No. 7467-954001, 9 May 1977.

3.0

TEST PLAN

The LACV-30-1 vehicle was tested in three phases. The first phase of testing was performed at the Bell Aerospace plant in Grand Bend, Ontario, Canada. The initial tests were performed overwater with a vehicle configuration which included volutes in both lift fan plenums and the lengthened Voyageur skirt system. These tests were the pre-delivery water tests performed on Lake Huron. The tests were performed under contract No. DAAK02-75-C-0149 Mod. No. P00007 CLIN No. 0006. The pre-delivery test results are presented in the report listed as 2.0(h) in the preceding section.

The second phase of testing was performed at the BAT facility adjoining the Niagara Falls International Airport in Wheatfield, N. Y. The modified skirt system was installed prior to these tests. The final phase of testing was performed at Ft. Story, Virginia.

The LACV-30-2 vehicle was tested in two phases, the first at the BAT facility in Wheatfield, N. Y., and the second at the Aberdeen Proving Grounds (APG) in Maryland.

The proposed type and acceptance tests to be performed on both vehicles are presented in Tables 3.1 and 3.2. These tests are outlined in Contract No. DAAK02-75-C-0149 which is listed as Item 2.0(a) in the preceding section. The actual tests performed on both vehicles are presented in Table 3.3. The swing crane acceptance test was only performed on LACV-30-1 because a swing crane was not installed on the LACV-30-2. Other tests performed but not included in Tables 3.1 and 3.2 are the skirt surveys and cabin contamination tests. The results of these tests are presented in the Appendix.

TABLE 3.1. TYPE AND ACCEPTANCE TESTS
(OVER LAND)

* TEST	(WT. AND L.C.G.)	SPEED (MPH)	SURFACE	METHOD
A Hover	60,000 lb., mid 115,000 lb., mid		Smooth Concrete	On cushion; record hover height and trim attitudes.
A SPEED RUNS	Any	30 - limit	Any	Surveyed course; distance/time up and down wind; increments of 5 mph
T Maneuvers	Any	Safe	Any	Figure - 8 turns.
T Obstacles	Any	Safe	Dirt	Negotiate prepared obstacle course consisting of hump varying from 1 to 3 ft. over length and 8 foot deep ditch varying in width from 3 to 6 feet over length. Courses from minimum to maximum.
T Prop Reversal Stop	Any	25	Any	Stop by propeller reversal at speeds of 10, 15, 20 and 25 mph.
A Swing Crane	Any		Smooth Concrete	Off cushion resting on landing pads with the engines at idle and APU operating to provide engine combustion air and electric power.

*A - Acceptance
T - Type

TABLE 3.2. TYPE AND ACCEPTANCE TESTS
(OVER WATER)

* TEST	LOADING (WT. AND L.C.G.)	SPEED (MPH)	WAVE HEIGHT	METHOD
A Hover	60,000 lb., mid 115,000 lb., mid	0	Calm	On cushion, record hover height and trim attitudes.
T Thrust Calibration	60,000 lb., mid	0	Calm	On and off cushion; tether aft. Using load cells, measure static Propeller Thrust at 70, 80, 90, 95 and 100%.
A Speed Runs	Any	30 - Limit	18 in.	Surveyed course; distance/time. Up and down wind runs; increments of 5 mph.
T Crash Stop	Any	30 - Limit	18 in.	Simulated engines (2) failures in 5 mph steps.
T Manuevers	Any	30 - Limit	12 in.	Figure -8 turns at increasing entry speeds; 5 mph step.
T Spin Out	Any	30 - Limit	6 in.	Simulated critical engine failure in 5 mph steps.
T Safe Operating Limits	All	AS req'd.	30 in.	To be determined. Progressive envelope expansion from Calm Water with optimum loading to limit wave height at maximum safe speed at fwd. L.C.G.

*A - Acceptance
T - Type

TABLE 3.3. COMPLETED TYPE AND ACCEPTANCE TESTS

<u>ACCEPTANCE TESTS</u>	<u>VEHICLE</u>	
	<u>LACV-30-1</u>	<u>LACV-30-2</u>
a) <u>OVER LAND</u>		
HOVER WITH FULL LOAD	X	X
HOVER WITH NO LOAD	X	X
GROUND SPEED	X	X
SWING CRANE	X	*
SYSTEM RUN-IN	X	X
b) <u>OVER WATER</u>		
HOVER WITH FULL LOAD	X	X
HOVER WITH NO LOAD	X	X
SPEED RUNS	X	X
<u>TYPE TESTS</u>		
a) <u>OVER LAND</u>		
CABIN NOISE LEVEL	X	X
SKIRT PRESSURE SURVEY	X	X
CABIN CONTAMINATION		X
OBSTACLE		X
MANEUVERING	X	
PROPELLER REVERSAL	X	
b) <u>OVER WATER</u>		
THRUST LOADING		X
AIR CONDITIONING		X
CABIN NOISE LEVEL	X	
MANEUVERING	X	
SAFE LIMITS	X	
ENGINE FAILURE CRASH	X	
ENGINE FAILURE SPINOUT	X	

*SWING CRANE NOT INSTALLED

4.0 TEST DATA AND ANALYSIS

4.1 TEST DATA

The test data for all the required acceptance and type tests are presented in four tables, two test phases for each vehicle. The initial test phase on the LACV-30-1 vehicle is not discussed here since it has been reported separately. Tables 4.1 and 4.2 present LACV-30-1 test data for tests performed at BAT and Ft. Story, Virginia. Tables 4.3 and 4.4 present LACV-30-2 test data obtained from tests at BAT and Aberdeen Proving Ground .

4.2 ANALYSIS

4.2.1 ACCEPTANCE TESTS

The analysis of the acceptance tests performed on the test vehicles is presented in the following subsections, where possible test data is compared to estimated values.

4.2.1.1 HOVER TESTS

Hover acceptance tests for both of the test vehicles were satisfactory. Both vehicles were tested with full and no load, on land and over water.

4.2.1.2 SPEED RUNS

The overland speed runs were required to be made in the speed range of 25 to 35 mph. The LACV-30-1 vehicle was tested at BAT and attained an average indicated air speed of 43.5 mph and a ground speed of 35 mph. The LACV-30-2 vehicle attained an average indicated air speed of 45 mph and ground speed of 36 mph.

The overwater speed test for the LACV-30-1 vehicle was performed at Ft. Story, Virginia. The vehicle attained a calibrated airspeed of 53 mph at a gross weight of 76,000 pounds. The power output of the ST6T-76 Twin Pac was 1701 horsepower. The power output was obtained using the TOP and N_2 readings taken during the test and inputting the data into the equation obtained from the Engine Operating Instructions listed in Section 2.0. The maximum speed of the LACV-30-1 with swing crane is presented in Figure 4.1 as a function of horsepower and average wave height for the test condition shown. The sea state

condition during the test was estimated as less than sea state 1 which means the average wave height was somewhere between 0 and 0.8 feet. The cross plot of 53 mph and 1701 horsepower in Figure 4.1 indicates an average wave height of 0.43 feet which basically verifies the speed attained.

The overwater speed test of the LACV-30-2 was performed at Aberdeen Proving Grounds. The comparison of estimated to average speed obtained in the test is shown in Figure 4.2. The average test speed of 42.5 mph is well below the predicted value of 51 mph for a 1200 horsepower lift fan and propeller input. The test data indicate that the speed runs were performed with a 2 mph cross wind. Although the cross wind is not significant, the variation of output horsepower for each Twin Pac is. According to the test data it appears that one Twin Pac was producing 1277 horsepower and the other 1121 horsepower which could indicate that propeller thrust was being used to control vehicle heading. The low power level for the test was due to operating the vehicle with uncompensated T7 limits. The vehicle engine normally operates with compensated T7 limits which for the values of T7 recorded during the test would normally indicate higher power output levels.

4.2.1.3 SWING CRANE LOADING TESTS

The swing crane loading tests were performed at BAT on the LACV-30-1 vehicle. The test is presented in Table 4.1. The swing crane was accepted with the provision that bow pre-loaders be installed to maintain pressure on the front landing pads during swing crane operation.

4.2.1.4 SYSTEM RUN-IN TESTS

System run-in tests were performed on both vehicles at BAT. The only discrepancy occurred in the LACV-30-1 vehicle where it was recommended that the existing horn be replaced and rechecked.

4.2.2 TYPE TESTS

The analysis of the type tests performed on the test vehicles is presented in the following subsections. Where possible test data are compared to estimated values.

4.2.2.1

CABIN NOISE LEVEL

Cabin noise level tests were performed on both vehicles, the LACV-30-1 overland and water, and the LACV-30-2 overland only. Noise spectra in octave bands were measured at crew stations of the LACV-30 at full power, with the craft both stationary on cushion and at maximum speed. Significant data obtained is compared below with "Steady-State Noise Limits for Personnel Occupied Areas", Category D in Table 2 of MIL-STD-1744A(MI).

Octave Band Center Frequency	Cat. D 8 Hr. Ex- posure (db)	Underway MCP (db)	Underway MAP (db)
125	96	94	99
250	89	91	94
500	83	84	89
1000	80	82	88
2000	79	75	81
4000	79	66	71
8000	81	63	69
db (A)	85	84-Computed-90	

The above shows the highest levels measured; underway at maximum continuous power (MCP) and at maximum available power (MAP), a power setting limited to five (5) minutes to prevent damage to the engines. Note that the prevailing full speed operation underway at MCP (2800 eshp) closely agrees to Category D standards which permits unprotected exposure for eight hours and is based primarily on hearing conservation priorities.

To judge the compatibility of the short duration higher levels at MAP, the Walsh-Healy Act safety regulations on industrial noise exposure equates db(A) sound level with exposure time by permitting a 5 db(A) increase in noise level with a 50% reduction in time exposed. Therefore, the noise measured at MAP (3700 eshp) is acceptable for a four (4) hour continuous exposure; engine operating limits restrict MAP to five (5) minutes.

The data taken with craft stationary (1600 eshp) is generally less than that experienced underway at MCP. At the lower frequencies, the decibel level is slightly above the underway cases most probably due to propeller blade pass noise at the effective zero pitch angle required to hover. Average levels measured comply with the specified standard.

4.2.2.2 MANEUVERING

Maneuvering tests were performed with the LACV-30-1 at Ft. Story. Turn radii on land were small, 15 ft. and 20 ft. in upwind and downwind tests. No estimates have ever been made for turning radii on land.

The overwater tests were performed for two entry speeds, 40 and 30 mph, at a gross weight of 76,000 pounds. The comparison of predicted with test data is shown in Figures 4.3 and 4.4. The turning radii obtained from the tests were estimated. The turning radius for an entry speed of 40 mph was in good agreement with predicted as shown in Figure 4.3. The turning radius for an entry speed of 30 mph was substantially lower than predicted as can be seen in Figure 4.4. Further testing at other test conditions would be required to substantiate the predicted values.

4.2.2.3 OBSTACLE TESTS

Obstacle crossing tests were performed at Aberdeen Proving Grounds using the LACV-30-2 vehicle. In the ditch crossing test the ditch measured 10 feet wide at the crossing point. The ditch crossing speed was an indicated air speed (IAS) of 22 mph. The second obstacle crossed was a three-foot high step. The test was performed at an IAS of 33 mph. The vehicle performed satisfactorily in both tests.

4.2.2.4 SAFE LIMITS

The safe operating limits overwater were performed to demonstrate that the vehicle would not "plow in" at selected speeds and yawed conditions. Tests were performed with the LACV-30-1 vehicle at entering yaw angles of 0 and 30 degrees at an IAS of 45 mph. No adverse behavior was recorded.

4.2.2.5 ENGINE FAILURE - "CRASH STOP"

"Crash stop" tests were performed overwater with the LACV-30-1 vehicle at Ft. Story. The tests were performed to demonstrate vehicle conditions with the loss of power from both engines. The tests were performed at a yaw angle of 0 degrees at a cut-off IAS of 40 mph and at a 30 degree yaw angle at a cut-off IAS of 45 mph. The vehicle exhibited no adverse behavior.

4.2.2.6 ENGINE FAILURE - "SPINOUT"

"Spinout" tests were performed on the LACV-30-1 vehicle at Ft. Story. The tests were performed to demonstrate the vehicle under a simulated engine failure condition with optimum trim from a target speed of 10-50 mph. The selected engine to be cut was at the discretion of the operator. The tests were performed at a yaw angle of 0 degrees at a cut-off IAS of 40 mph and a yaw angle of 30 degrees with a cut-off IAS of 30 mph. After engine cut-off the vehicle yawed in the direction of the cut-off engine and sideslipped until the operator took corrective action. The estimated maximum roll angle incurred during the test was 25 degrees. The corrective action taken by the operator for restoring vehicle control was to reduce power on the opposite engine. The recovery action successfully corrected the unusual vehicle attitude.

4.2.2.7 THRUST LOADING

The thrust loading test was performed at APG with the LACV-30-2 vehicle hovering overwater. The vehicle was tethered to a government furnished measuring device to determine thrust of the 43D50-363 propeller over a range of engine settings. Due to the inability of maintaining the vehicle normal to the tether point, the values obtained in the test were not considered to be the maximum available.

The test was repeated overland. The vehicle was tethered at the stern to a GFE thrust measurement van which was used to determine the net forward force. A bridle on the starboard side restrained the vehicle from lateral movement. A total of seven test points were obtained. The test conditions were:

T_{AMB}	= 80°F
V_{WIND}	= 4 MPH
BAROMETER	= 29.95 inHg
W_G	= 85,000 Lb. (empty MILVAN's placed on deck)

The results of the analysis are presented in Table 4.5. The predicted propeller data provided by Hamilton Standard has a minimum C_p value of 0.07, therefore no comparison to predicted can be made for the first three test points. Test points 4, 5 and 6 indicate that the resulting performance of the propellers was within 10% of the predicted, while the test point 7 was within 3% of predicted. No angles of attack were recorded during the test, therefore cushion thrust effects have not been included in the analysis.

4.2.2.8 AIR CONDITIONING

Air conditioning tests were performed overwater on the LACV-30-2 vehicle at Ft. Story. The outside temperature was 101°F. At the end of the test, 30 minutes later, the cabin temperature dropped to 78°F. The test results were satisfactory and accepted by the U. S. Army.

4.2.2.9 PROPELLER REVERSAL

The overland stop tests were performed on the LACV-30-1 vehicle at BAT. The propeller reverse thrust was used to stop the craft. The stopping time from an IAS of 45 mph was 56 seconds. The stopping distance was 1600 feet. The test results were accepted by the U. S. Army.

4.2.2.10 CABIN CONTAMINATION

The cabin contamination tests were performed on the LACV-30-2 vehicle at BAT. The data is presented in Appendix A. The measured noxious fumes were in allowable limits and were acceptable for habitation.

4.2.2.11 SKIRT PRESSURE SURVEY

The skirt pressure survey was performed at BAT on both of the test vehicles. The tests were not required as part of the acceptance test program. The report presenting the test data and results is presented in Appendix B to provide a complete data package for both of the vehicles.

TABLE 4.1. LACV-30-1 TESTS AT BAT

THIS TABLE CONSISTS OF A SERIES OF TEST PLANS
FOLLOWED BY TEST DATA.

BELL AEROSPACE ACV TEST PLAN			TYPE LACV-30-1		OPER. NO. A1-0218	
ACV CREW		NO CHASE AIRCRAFT		TEST CONDITIONS		
CREW POSITION	NAME	TYPE A/C	CREW		TAKEOFF	LAND
Operator	D. Hall			WEIGHT	115,000	TBD
Co-Operator	G. Yaeger			FUEL	See Loading 4	
U.S.A. Obs.	J. Sargent			C.G.	-	-
	H. Woods	INSTRUMENTATION PLAN NONE		BALLAST	-	-
	L/C Pope	SETUP NO.	AMEND NO.	ALT SETTING		
		RADIO FREQ.		PRESS ALT		
TEST ENGINEER	C. Stauffer	UHF	121.7	WIND		
TEST DIRECTOR	"	UHF-FM	6	TEMP		
FINAL GO-NO GO AUTHORITY	"	VHF-FM	TBD	RECORD ABOVE DATA		
CRAFT CHANGES SINCE LAST OPERATION Air Management Instrumentation removed (less pressure taps).				TEST PURPOSE A. Demonstration to U.S. Army for acceptance: 1. Hover with full load. 2. System run-in tests 3. Cabin noise level (stationary)		
TEST ENGINEER <i>C. L. Stauffer</i>		OPER. IN COMMAND		APPROVAL <i>J. Sargent</i>		
TEST PROCEDURE						
I. Position craft on BAC concrete ramp north of production hangar. restrain as required for wind and slope. II. Perform Operator Inspection IAW Checklist. III. Perform normal pre-start, start, etc. IAW Checklists. IV. Raise craft in hover mode A. Conduct acceptance tests (DAAK02-75-C-0149, Attachment I, Pages 10 and 11). 1. Hover with full load per Attachment I (Ref. Item 9(A)2)A. 2. Perform system run-in tests per Attachment 2 (Ref. Item 9(A)3)A & B). 3. Obtain cabin noise level data per Attachment 3 (Ref. Item 9(A)5) V. Secure craft as required for cargo handling tests.						

U.S. ARMY ACCEPTANCE

LACV-30-1

LAND HOVER WITH FULL LOAD

1. Verify craft configured per Loading 4 (115,000 lb. G.W.).
2. In cushion mode, trim and perform a 15 minute demonstration at N₂ maximum (91% N₂ minimum).
3. Manually record the following data:

	<u>START</u>				<u>COMPLETE</u>			
Time	<u>1530</u>				<u>1640</u>			
Fuel (Fwd)	<u>54%</u>	<u>54%</u>			<u>54%</u>	<u>54%</u>		
(Main)	<u>80%</u>	<u>75%</u>			<u>75%</u>	<u>75%</u>		
(Aft)	<u>52%</u>				<u>52%</u>			
T ₇ (°C)	<u>405</u>	<u>465</u>	<u>450</u>	<u>420</u>	<u>405</u>	<u>465</u>	<u>450</u>	<u>420</u>
N ₁ (%)	<u>85.5</u>	<u>89.0</u>	<u>86.5</u>	<u>86.0</u>	<u>85.5</u>	<u>89.0</u>	<u>86.5</u>	<u>86.0</u>
N ₂ (%)	<u>91</u>	<u>91</u>	<u>91</u>	<u>91</u>	<u>91</u>	<u>91</u>	<u>91</u>	<u>91</u>
Torque (psi)	<u>18</u>	<u>18</u>	<u>16</u>	<u>18</u>	<u>18</u>	<u>16</u>	<u>18</u>	

COMMENTS:

All operations satisfactory.

COMPLETED

BAC

VERIFIED

BAC QUALITY

ACCEPTED

U.S.A. REPRESENTATIVE

19 Feb 76

U.S. ARMY ACCEPTANCE

LACV-30-1

SYSTEM RUN-IN TESTS

1. Starting concurrent with Hover (Attachment 1) and continuing off cushion for a total of one hour, functionally operate the following systems:

Start Time	1530	Complete Time	1640
Puff Ports (20 cycles each)		<i>[Signature]</i>	<i>[Signature]</i> (19 Feb 76)
Cabin Heaters (Both, Lo and Hi)		<i>[Signature]</i>	<i>[Signature]</i>
Windshield Heat (Continuous)		<i>[Signature]</i>	<i>[Signature]</i>
Air Conditioner (Vent & Cool)		<i>[Signature]</i>	<i>[Signature]</i>
APU (Generator On)		<i>[Signature]</i>	<i>[Signature]</i>
AN/URC-80 (4 Contacts)		<i>[Signature]</i>	<i>[Signature]</i>
AN/URC-46 (4 Contacts)		<i>[Signature]</i>	<i>[Signature]</i>
AN/PRC-94 (4 Contacts)		<i>[Signature]</i>	<i>[Signature]</i>
RMHS System (Continuous)		<i>[Signature]</i>	<i>[Signature]</i>
AN/ASN-43 Compass (Continuous)		<i>[Signature]</i>	<i>[Signature]</i>
Radar (Continuous)		<i>[Signature]</i>	<i>[Signature]</i>
Fuel Trim (To/From Transfers)		<i>[Signature]</i>	<i>[Signature]</i>
Engines (Continuous)		<i>[Signature]</i>	<i>[Signature]</i>
Propellers (As Required)		<i>[Signature]</i>	<i>[Signature]</i>
Windshield Wipers (4 Cycles)		<i>[Signature]</i>	<i>[Signature]</i>
Spotlight (4 Cycles)		<i>[Signature]</i>	<i>[Signature]</i>
Running Lights (Continuous)		<i>[Signature]</i>	<i>[Signature]</i>
Horn (4 Blasts)			
		BAC	U.S.A.

DISCREPANCIES AND DISPOSITION:

RMHS operative; needs repeat Compass Swing. Will be accomplished during BAC tests at Fort Storey.

Existing horn will be replaced; recheck as above.

COMPLETED

[Signature]
BAC

VERIFIED

[Signature]
BAC QUALITY

ACCEPTED

[Signature]
U.S.A. REPRESENTATIVE

19 Feb 76

U.S. ARMY ACCEPTANCE

LACV-30-1

CABIN NOISE LEVEL - STATIONARY

1. Concurrent with Attachment 1, conduct survey with engines at full power (N₂ maximum). Using an Octave-Band Noise Analyzer, record noise levels at ear level.

Band		<u>Operator</u>		<u>Freq.</u>	<u>Passenger</u>	
		(Raw)	(Corr.)	(Hertz)	(Raw)	(Corr.)
1		<u>48</u>	<u>48.9</u>	16000	<u>48</u>	<u>48.9</u>
2		<u>60</u>	<u>60</u>	8000	<u>60</u>	<u>60</u>
3		<u>61</u>	<u>58</u>	4000	<u>60</u>	<u>57</u>
4		<u>68</u>	<u>68.2</u>	2000	<u>67</u>	<u>67.2</u>
5		<u>74</u>	<u>74</u>	1000	<u>73</u>	<u>73</u>
6		<u>82</u>	<u>81.8</u>	500	<u>82</u>	<u>81.8</u>
7		<u>92</u>	<u>92</u>	250	<u>94</u>	<u>94</u>
8		<u>125</u>	<u>125.7</u>	125	<u>105</u>	<u>105.6</u>

Record engine parameters.

N ₁ (%)	<u>85.5</u>	<u>89.0</u>	<u>86.5</u>	<u>86.0</u>
N ₂ (%)	<u>91</u>	<u>91</u>	<u>91</u>	<u>91</u>
Torque (psi)	<u>17</u>	<u>18</u>	<u>16</u>	<u>18</u>
Prop. Pitch	<u>-5</u>	<u>-5</u>		

Record Model and Serial No. of Test Equipment.

General Radio Model 1558AP Octave Band Noise Analyzer, S/N 732.

Attach Calibration Sheets.

COMPLETED

BAC

VERIFIED

BAC QUALITY

ACCEPTED

U.S.A. REPRESENTATIVE

Bell Aerospace Company

TEXTON

POST OFFICE BOX ONE • BUFFALO, NEW YORK 14240

CALIBRATION
PROCEDURE
NUMBER 90644
REVISION

CALIBRATION DATA SHEET

NOMENCLATURE <u>CTAVE BANDWIDTH AND SIZE</u>	MANUFACTURER <u>GEN. RADIO</u>	MODEL NO. <u>1558-AP</u>
FILE NO. <u>3260053</u>	TECH. <u>S.R. MITROWSKI</u>	CALIB. DATE <u>5-19-75</u>

CALIBRATION EQUIPMENT

FILE NO.			
1050002	STUM	HP	300
1910003	DELTA ATTEN	HP	400D
2580002	OSC	HP	1450
2050003	OSC	HP	205AC
3250001	CONTR	B. REEF	200CO
3010001	ALC RAMP CAL	HP	7370
	TRANSFORMER	HP	15540
	MISOPHONIC	HP	2995-1131

CALIBRATION DATA

PARA. STEP NO.	FUNCTION TESTED	MEASUREMENT DATA			TOLERANCES
		NOMINAL	MEASURED	CORRECTED	
	RAMP LEVEL DB				
	OUTER DIAL				
	POS	STD SET			±1.0DB
	50 (6)	40	Wing		
	60 (5)	80			
	70 (4)	70	-0.2		
	80 (3)	60	-0.1		
	90 (2)	50	-0.1		
	100 (1)	40	REF DB		
	(1)	30	-0.1		
	(1)	20	-0.1		
	(1)	10	-0.1		
	(1)	0	-0.1		±1.0DB
	METER CHECK				
	OUTER DIAL				
	POS 4 (OUT)	STD SET			
	(4)	45	-5.0		
	(4)	44	-4.0		
	(4)	42	-2.0		
	(4)	40	REF 0		
	(4)	38	+2.0		
	(4)	36	+4.0		
	(4)	32	+8.0		
	(4)	30	+10.0		

CALIBRATION DATA

612 1558 AKS

PARAM. TEST NO.	FUNCTION TESTED	MEASUREMENT DATA			TOLERANCES
		NOMINAL	MEASURED	CORRECTED	
	BAND PASS FILTER	1 KHz			
	1/2 LOW CUTOFF	11.15	>30 dB		>30 DB
	LOW CUTOFF	22.3	-3.0		3.5 DB $\pm 1 DB$
	315 CENT FREQ	31.5	1.0 dB		$\pm 1 DB$
	HIGH CUTOFF	44.6	2.5 "		3.5 DB $\pm 1 DB$
	2X HIGH CUTOFF	89.2	>30 "		>30 DB
	1/2 LOW	22.3	>30 dB		>30 DB
	LOW	44.6	-3.0 "		3.5 DB $\pm 1 DB$
63	CENT FREQ	63	-0.8 "		$\pm 1 DB$
	HIGH	89.2	-2.6 "		3.5 DB $\pm 1 DB$
	2X HIGH	178.4	>30. "		>30 DB
	1/2 LOW	44.6	>30 dB		>30 DB
	LOW	88.4	-2.4 "		3.5 DB $\pm 1 DB$
125	CENT FREQ	125	+0.7 "		$\pm 1 DB$
	HIGH	177	-3.0 "		3.5 DB $\pm 1 DB$
	2X HIGH	354	>30. "		>30 DB
	1/2 LOW	88.4	>30 dB		>30 DB
	LOW	177	-2.2 " *		3.5 DB $\pm 1 DB$
250	CENT FREQ	250	0.0 "		$\pm 1 DB$
	HIGH	354	-3.0 "		3.5 DB $\pm 1 DB$
	2X HIGH	707	>30. "		>30 DB
	1/2 LOW	177	>30 dB		>30 DB
	LOW	354	-2.2 " *		3.5 DB $\pm 1 DB$
500	CENT FREQ	500	-0.2 "		$\pm 1 DB$
	HIGH	707	-4.0 "		3.5 DB $\pm 1 DB$
	2X HIGH	1414	>30 "		>30 DB
	1/2 LOW	354	>30 dB		>30 DB
	LOW	707	-2.8 "		3.5 DB $\pm 1 DB$
1000	CENT FREQ	1000	0.0 "		$\pm 1 DB$
	HIGH	1414	-4.0 "		3.5 DB $\pm 1 DB$
	2X HIGH	2828	>30. "		>30 DB
	1/2 LOW	707	>30 dB		>30 DB
	LOW	1414	-2.0 " *		3.5 DB $\pm 1 DB$
2000	CENT FREQ	2000	+0.2 "		$\pm 1 DB$
	HIGH	2828	-3.0 "		3.5 DB $\pm 1 DB$
	2X HIGH	5656	>30. "		>30 DB
	1/2 LOW	2828	>30 dB		>30 DB
	LOW	5656	-4.5 "		3.5 DB $\pm 1 DB$
4000	CENT FREQ	4000	0.0 "		$\pm 1 DB$
	HIGH	5610	-3.2 "		3.5 DB $\pm 1 DB$
	2X HIGH	11220	>30. "		>30 DB
	1/2 LOW	5656	>30 dB		>30 DB
	LOW	11310	-2.8 "		3.5 DB $\pm 1 DB$
16000	CENT FREQ	16000	+0.9 "		$\pm 1 DB$
	HIGH	22620	-3.0 "		3.5 DB $\pm 1 DB$
	2X HIGH	45240	>30. "		>30 DB
	1/2 LOW	1414	>30 dB		>30 DB
	LOW	2828	-1.6 " *		3.5 DB $\pm 1 DB$
4000	CENT FREQ	4000	+0.8 "		$\pm 1.0 DB$
	HIGH	5656	-3.0 "		3.5 DB $\pm 1 DB$
	2X HIGH	11320	>30. "		>30 DB

* LIMITED USE

BELL AEROSPACE ACV TEST PLAN		TYPE LACV-30-1		OPER. NO. A2-0219	
ACV CREW		NO CHASE AIRCRAFT		TEST CONDITIONS	
CREW POSITION	NAME	TYPE A/C	CREW		TAKEOFF LAND
Operator	Hall			WEIGHT	Not applicable
Co-Operator	Yaeger			FUEL	
Crew	Finch			C.G.	
"	Greenspan	INSTRUMENTATION PLAN		BALLAST	See Loading 4
U.S.A. Obs.	J. Sargent	SETUP NO.	AMEND NO.	ALT SETTING	
		RADIO FREQ.		PRESS ALT	
TEST ENGINEER	Stauffer	Not Required		WIND	
TEST DIRECTOR	"			TEMP	
FINAL GO-NO GO AUTHORITY	"			RECORD ABOVE DATA	
CRAFT CHANGES SINCE LAST OPERATION NONE				TEST PURPOSE A. Demonstration to U.S. Army for acceptance: 1. Off load 2 MILVANS with swing crane.	
TEST ENGINEER <i>C. I. Stauffer</i>		OPER. IN COMMAND		APPROVAL <i>J. Sargent</i>	
TEST PROCEDURE					
<p>I. Position craft on BAC concrete ramp. In the event of adverse weather, hangar craft on North Side of Flight Test Hangar. (In hangar, external 400 hertz power to be used in lieu of APU.)</p> <p>II. Perform Operator Inspection IAW Checklist.</p> <p>III. Perform sections of normal pre-start, start, etc. required for APU (Generator On) operation. Man the operators position for periods when APU is operating.</p> <p>IV. With craft on landing pads: A. Conduct acceptance tests (DAAK02-75-C-0149, Attachment I, Page 11) 1. Swing crane off-load MILVANS per Attachment 1 (Ref. Item 9(A)6).</p> <p>V. Secure craft and prepare for taxi tests (A3-0220).</p>					

Bell Aerospace **TEXTRON**

Bell Aerospace Division of Textron Inc.

Post Office Box One
Buffalo, New York 14240
716/297-1000

B. Swing Crane Operations

The LACV-30 will be off cushion resting on its landing pads with the engines at idle and the APU operating to provide engine combustion air and electrical power. Observe precautions in Chapter 2, Section 3. The basic functions and sequence are as follows:

- (1) The crewmen exit the cabin.
- (2) Unlash the MILVANS.
 - (a) Slide the lock and pull handle on tensioner assembly to open position.
 - (b) Remove beaded assembly from tensioner.
 - (c) Remove beaded assembly from the MILVAN corner fitting.
 - (d) Remove tensioner assembly from the cargo tiedown fitting by removing the screw pin from the shackle and removing the shackle from the deck fitting. Reinstall the screwpin.
 - (e) Stow all lashings.
- (3) Unlash load spreader pallets.
 - (a) Slip lines from the bollard.
 - (b) Unhook the line from pallet "D" ring.
 - (c) Stow all lines.
- (4) Unlash chain hoists and lifting beams, stow lashings.
- (5) Pull pins on outboard surf fence struts, swing forward and stow and repin. Install surf fence locks between surf fence sections.
- (6) Pull swing crane transportation stow pins.

Bell Aerospace **TEXTRON**

Bell Aerospace Division of Textron Inc.

Post Office Box One
Buffalo, New York 14240
716/297-1000

- (7) Engage tow chain in pallet chain fitting (2 forward pallets) and pin in position. Place tail of chain on pallets. Raise pallet tierod to UP position.
- (8) Start hydraulic power unit.

WARNING

KEEP HANDS AND FEET CLEAR OF MOVING CHAIN, PULLEY, TIEROD AND HYDRAULIC ACTUATOR, ASSURE PALLETS AND CHAIN DO NOT SNAG OR JAM DURING FORWARD MOVEMENT.

- (9) Operate swing crane forward. The two forward pallets and MILVAN will move forward approximately 13 ft.

WARNING

KEEP HANDS AND FEET CLEAR OF MOVING OR ROTATING EQUIPMENT.

- (10) Operate swing crane aft, disengage pin and chain from both pallets, replace in, and simultaneously pull the port and starboard chain aft keeping the chain under tension and free of obstructions.
- (11) Stop the crane when the limit blocks are aft of the pallet tow chain fittings.
- (12) Re-engage tow chains in the pallet tow fittings. The nylon limit block must be forward of the tow fitting and as close to the fitting as possible with an equal number of links between fittings and limit blocks port and starboard. Replace pin. Place tail of chain on pallets.

WARNING

IF, DUE TO POSITION OF MILVAN ON PALLET, THE TIEROD WILL HIT THE SURF FENCE STRUTS — REMOVE THE TIEROD AND STORE ON FWD. DECK.

Bell Aerospace **TEXTRON**

Bell Aerospace Division of Textron Inc.

Post Office Box One
Buffalo, New York 14240
716/297-1000

- (13) Operate swing crane to position the front edge of MILVAN at guide mark on deck.
- (14) Position swing crane to VERTICAL POSITION.
- (15) Disengage chain from pallet tow fitting both sides. Replace pin.
- (16) Attach snatch block from winch swing crane to jack assembly.
- (17) Unlock jack and lower to ground.
- (18) Repeat for opposite jack.
- (19) Rotate jack pad 90 degrees. Jack swing crane tierod end to top of lateral support fitting.
- (20) Repeat for opposite jack and secure winch.
- (21) Operate swing crane to full aft position, simultaneously pulling the tow chain aft keeping the chain under tension and free of obstructions.
- (22) Lower chain fall and lifting beam to top of MILVAN and engage beam hooks in MILVAN. Raise chain-fall to pretension the hooks.

CAUTION

BE CERTAIN BOW TRUNK SKIRTS ARE UNDER THE CRAFT
SO TRAILER DOES NOT RUN OVER THEM.

- (23) Move tractor/trailer into position.

WARNING

ENSURE THAT THE TOW CHAINS DO NOT CATCH ON PALLETS,
CURBS. TIEDOWN FITTINGS OR THE HOIST HAND CHAIN
DOES NOT ENGAGE THE SURF FENCE.

Bell Aerospace **TEXTRON**

Bell Aerospace Division of Textron Inc.

Post Office Box One
Buffalo, New York 14240
716/297-1000

- (24) Operate swing crane to lift MILVAN from the deck to the trailer.
- (25) Lower chain fall and position MILVAN on trailer. Use tag lines if required.
- (26) Disengage beam hooks from the MILVAN and operate chain hoist to raise the beam back up to position.

When only one MILVAN is to be unloaded, proceed to step 45. If a second MILVAN is to be unloaded, proceed as follows:

- (27) Operate swing crane to aft position simultaneously pulling the tow chains aft keeping tension on the chains and free of obstructions.

NOTE

TRAILER CAN BE MOVED OUT.

- (28) Remove pallet tierods and place on fwd deck.
- (29) Attach pallet tiedown ropes to "D" rings of pallets and position pallets to center of deck.
- (30) Engage tow chain in pallet chain fitting (2 aft pallets) and pin in position. Place tail of chain on pallets. Raise pallet tierod to UP position.

WARNING

KEEP HANDS AND FEET CLEAR OF MOVING CHAIN, PULLEY, TIEROD AND HYDRAULIC ACTUATOR. ASSURE PALLETS AND CHAIN DO NOT SNAG OR JAM DURING FORWARD MOVEMENT.

- (31) Operate swing crane forward. The two pallets and MILVAN will move forward approximately 13 ft.

WARNING

KEEP HANDS AND FEET CLEAR OF MOVING OR ROTATING EQUIPMENT.

Bell Aerospace **TEXTRON**

Bell Aerospace Division of Textron Inc.

Post Office Box One
Buffalo, New York 14240
716/297-1000

- (32) Operate swing crane aft, disengage pin and chain from both pallets, replace pin, and simultaneously pull the port and starboard chain aft keeping the chain under tension and free of obstruction.
- (33) Reengage tow chains in pallet chain fittings and pin in position. Place tail of chains on pallets.

WARNING

KEEP HANDS AND FEET CLEAR OF MOVING CHAIN, PULLEY, TIEROD AND HYDRAULIC ACTUATOR. ASSURE PALLETS AND CHAIN DO NOT SNAG OR JAM DURING FORWARD MOVEMENT.

CAUTION

ASSURE THE PALLET TIEROD IS IN THE UP POSITION AND OBSERVE THAT TIEROD AND MILVAN TRAVERSE THE TWO PALLETS ON CENTER OF DECK.

- (34) Operate swing crane forward.

WARNING

KEEP HANDS AND FEET CLEAR OF MOVING OR ROTATING EQUIPMENT.

- (35) Operate swing crane aft, disengage pin and chain from both pallets, replace pin, and simultaneously pull the port and starboard chain aft keeping the chain under tension and free of obstructions.
- (36) Stop the crane when the nylon limit blocks are aft of the pallet tow chain fittings.
- (37) Re-engage tow chains in the pallet tow fittings. The nylon limit block must be forward of the tow fitting and as close to the fitting as possible with an equal number of links between fittings and limit blocks port and starboard. Replace pin. Place tail of chain on pallets.

Bell Aerospace **TEXTRON**

Bell Aerospace Division of Textron Inc.

Post Office Box One
Buffalo, New York 14240
716/297-1000

- (38) Operate swing crane to position the front edge of MILVAN at guide mark on deck. As the pallets/MILVAN moves forward observe the tierod assembly in the lateral support fitting. If the rod assembly moves out of the supporting fitting, adjust the jacks to lower the tierod assembly back into position.
- (39) Operate swing aft, disengage chain from pallet tow fitting both sides. Replace pin and pull tow chains aft.
- (40) Lower chain fall and lifting beam to top of MILVAN and engage beam hooks in MILVAN. Raise chain fall to pretension the hooks.

CAUTION

BE CERTAIN BOW TRUNK SKIRTS ARE UNDER THE CRAFT SO TRAILER DOES NOT RUN OVER THEM.

- (41) Move tractor/trailer into position.

WARNING

ENSURE THAT THE TOW CHAINS DO NOT CATCH ON PALLETS, CURBS OR TIEDOWN FITTINGS.

- (42) Operate swing crane to lift MILVAN from the deck to the trailer.
- (43) Lower chain fall and position MILVAN on trailer. Use tag lines if required.
- (44) Disengage beam hooks from the MILVAN and operate chain hoist to raise the beam back up to position.
- (45) Operate the swing crane to the vertical position simultaneously pulling the chains aft. Keeping tension on the chains and free of obstruction.

Bell Aerospace **TEXTRON**

Bell Aerospace Division of Textron Inc.

Post Office Box One
Buffalo, New York 14240
716/297-1000

NOTE

MOVE THE TRAILER OUT.

- (46) Raise the jack pads and repin the tierods in the lateral support fitting, both sides.
- (47) Attach the winch hook to the jack and hoist to the stow position and latch onto the gantry.
- (48) Repeat for opposite jack and secure winch.
- (49) Reposition and repin surf fence struts. Remove surf fence locks and stow.
- (50) Operate swing craft aft simultaneously pulling the chains aft. Keeping tension on chains and free of obstructions.
- (51) Attach pallet tiedown ropes and manually pull aft pallets to position as marked on deck.
- (52) Repeat for the fwd pallets.
- (53) Secure the chain hoists and lift beams.
- (54) Lash pallets to deck with 4-150070-33 rope assemblies.
- (55) Reposition the pallet tierods between the aft pallets and between the fwd pallets.
- (56) Secure the tow chains.

U.S. ARMY ACCEPTANCE

LACV-30-1

SWING CRANE MILVAN OFF-LOAD

The acceptance tests as defined in this attachment were accomplished.

COMMENTS:

Accepted with understanding that a hydraulic actuation will insure contact of the forward skids with ground surface when a fully loaded milvan (44,800 lbs) is over center, forward, to prevent load runaway.

COMPLETED C. J. Sargent
BAC

ACCEPTED C. J. Sargent
U.S.A. REPRESENTATIVE
19 Feb 76

VERIFIED Joe Mueller 2/19/76
BAC QUALITY

BELL AEROSPACE ACV TEST PLAN		TYPE LACV-30-1		OPER. NO. A3-0220	
ACV CREW		NO CHASE AIRCRAFT		TEST CONDITIONS	
CREW POSITION	NAME	TYPE A/C	CREW		TAKEOFF
Operator	Hall			WEIGHT	TBD
Co-Operator	Yaeger			FUEL	Loading No. 5
U.S.A. Obs.				C.G.	-
		INSTRUMENTATION PLAN		BALLAST	0
		None		ALT SETTING	0
		SETUP NO.	AMEND NO.		
		RADIO FREQ.		PRESS ALT	
TEST ENGINEER	Stauffer	VHF	121.7	WIND	
TEST DIRECTOR	"	VHF-FM	P 55.85 S 85.55	TEMP	
FINAL GO-NO GO AUTHORITY	"	UHF-FM	6	RECORD ABOVE DATA	
CRAFT CHANGES SINCE LAST OPERATION MILVANS and associated hardware removed.				TEST PURPOSE A. Demonstration to U.S. Army for acceptance: 1. Hover with no load. 2. Maneuvering (8's). 3. Speed Run (25-35 mph) 4. Prop Reversal Stop from > 25 mph.	
TEST ENGINEER <i>C. J. Stauffer</i>		OPER. IN COMMAND		APPROVAL <i>J. Hargrett</i>	
TEST PROCEDURE					
I. Position craft on BAC concrete ramp north of Production Hangar. Restrain as required for wind and slope.					
II. Perform Operator Inspection IAW Checklist.					
III. Perform normal pre-start, start, etc. IAW Checklists.					
IV. Operate craft and systems as required:					
A. Conduct acceptance tests (DAAK02-75-C-0149, Attachment I, Page 11)					
1. Hover without load per Attachment 1 (Ref. Item (9)(a)2)a)					
2. After release of restraints, taxi to preselect area on NFIAP. Maneuver (8's) per Attachment 2 (Ref. Item (9)(a)2)c)					
3. Perform speed runs per Attachment 3 (Ref. Item (9)(a)2)b)					
4. On any 25 mph run, accomplish stop using full propeller reversal per Attachment 4 (Ref. Item (9)(a)2)e).					
V. Return to BAC Ramp and secure craft.					

U.S. ARMY ACCEPTANCE

LACV-30-1

OVERLAND HOVER WITHOUT LOAD

1. Verify craft configured per loading 5 ($\approx 85,000$ lb. G.W.).
2. In cushion mode, trim and perform a 15 minute demonstration at N₂ maximum (91% N₂ minimum).
3. Manually record the following data:

	<u>START</u>				<u>COMPLETE</u>			
Time	<u>1,342</u>				<u>1,357</u>			
Fuel (Fwd)	<u>55%</u>	<u>55%</u>	<u>55%</u>	<u>55%</u>	<u>55%</u>	<u>55%</u>	<u>55%</u>	<u>55%</u>
(Main)	<u>65%</u>	<u>65%</u>	<u>65%</u>	<u>65%</u>	<u>65%</u>	<u>65%</u>	<u>65%</u>	<u>65%</u>
(Aft)	<u>48%</u>				<u>48%</u>			
T7 (°C)	<u>405</u>	<u>460</u>	<u>450</u>	<u>430</u>	<u>405</u>	<u>460</u>	<u>450</u>	<u>430</u>
N ₁ (%)	<u>85.0</u>	<u>87.5</u>	<u>87.0</u>	<u>86.0</u>	<u>85.0</u>	<u>87.</u>	<u>87.</u>	<u>86.</u>
N ₂ (%)	<u>91</u>	<u>91</u>	<u>91</u>	<u>91</u>	<u>91</u>	<u>91</u>	<u>91</u>	<u>91</u>
Q (psi)	<u>22</u>	<u>22</u>	<u>21</u>	<u>25</u>	<u>22</u>	<u>22</u>	<u>21</u>	<u>25</u>

COMMENTS:

COMPLETED

BAC

ACCEPTED

U.S.A. REPRESENTATIVE

VERIFIED

QUALITY

U.S. ARMY ACCEPTANCE

LACV-30-1

OVERLAND MANEUVERING (8's)

1. Determine wind direction in the test area.
2. At a safe maneuvering ground speed (5 to 10 mph) perform "8" approximately up and down wind.
3. Record time through each (2) 360°.

Upwind 15 Secs. Downwind 20 Secs.

4. Record wind direction 260 Velocity 5 mph.

5. As practicable, record turn radii.

Upwind 15 Ft. Downwind 20 Ft.

6. COMMENTS:

COMPLETED

C. L. Staffer
BAC

ACCEPTED

Harold B. 20 Feb 76
U.S.A. REPRESENTATIVE

VERIFIED

Ira Mueller 2/20/76
BAC QUALITY

U.S. ARMY ACCEPTANCE

LACV-30-1

OVERLAND SPEED RUNS (25 TO 35 mph)

1. Determine wind direction in the Test Area.
2. Record Wind Direction 260, Velocity 5 mph.
3. On wind dependent course selected, perform two reciprocal runs at speed from 25 to 35 mph (estimated).
4. Record IAS, ground speeds attained and measurement method (pacer, time/dist., other).

	<u>IAS (mph)</u>	<u>GS (mph)</u>	<u>Method</u>
Run 1	<u>42</u>	<u>37</u>	<u>Time Distance</u>
Run 2	<u>45</u>	<u>33</u>	<u>" "</u>
Average	<u>43.5</u>	<u>35</u>	<u>" "</u>

5. COMMENTS:

COMPLETED

C. J. Stiff
BAC

ACCEPTED

Harold J. 20 Feb 76
U.S.A. REPRESENTATIVE

VERIFIED

Fred Muller 2/20/76
BAC QUALITY

U.S. ARMY ACCEPTANCE

LACV-30-1

OVERLAND STOP (>25 mph)

1. In conjunction with "OVERLAND SPEED RUNS" (Attach. 3), perform a stop from any attained speed over 25 mph using normal propeller reversal techniques.

2. Record

Attained Speed (mph)	<u>45</u> IAS	<u>37</u> GS
Stopping Distance	<u>1,600</u> Ft.	<u>Scale</u> (Method)
Stopping Time	<u>56</u> Sec.	
Inst. Obs. (Av.)	<u>RUN</u> (Reference	<u>STOP</u> (Max.)
T ₇ (°C)	<u>450</u>	<u>450</u>
N ₁ (%)	<u>-</u>	<u>-</u>
N ₂ (%)	<u>92</u>	<u>92</u>
Q (psi)	<u>34</u>	<u>36</u>

3. COMMENTS

COMPLETED

C. L. Staffer
BAC

ACCEPTED

20 Feb 76
U.S.A. REPRESENTATIVE

VERIFIED

Fred Mueller 2/20/76
BAC QUALITY

TABLE 4.2. LACV-30-1 TESTS AT FT. STORY

THIS TABLE CONSISTS OF A SERIES OF TEST PLANS
FOLLOWED BY TEST DATA.

BELL AEROSPACE ACV TEST PLAN			TYPE LACV-30-1		OPER. NO. A1-0114(1977)	
ACV CREW		NO CHASE AIRCRAFT		TEST CONDITIONS		
CREW POSITION	NAME	TYPE A/C	CREW		TAKEOFF	LAND
Operator	D. Hall			WEIGHT	76,000	
Oper. Nav.	Maj. R. Layman			FUEL	As No 7	
Obs.	L.T. R. L. L. L.			C.G.	447	
Obs.	G. Penn	INSTRUMENTATION PLAN OCTAVE BAND ANAL.		BALLAST	None	
Obs./C.O.R.	G. Sargent	SETUP NO. N/A	AMEND NO. N/A	ALT SETTING	30.14	
		RADIO FREQ.		PRESS ALT	S.L.	
TEST ENGINEER	C. Stauffer	URC-80	VRC-46	WIND	L/V	
TEST DIRECTOR	C. Stauffer	P	P	TEMP	-135F	
FINAL GO-NO GO AUTHORITY	C. Stauffer	S	S	Sea State	2	
CRAFT CHANGES SINCE LAST OPERATION				TEST PURPOSE		
1. Connected STD Pipe to Teller's Water hose replacing high pressure pump. Also change relief valve. Fuel Quantity P S F 57% 12.5 M 35 35 A 42.5				I. Water hover (15 minutes) II. Speed runs (30-50 mph) III. Cabin Noise Level (V max.) IV. Maneuvering 8's (30-50 mph) V. Safe Limits VI. Engines failure/crash stop (30-50 mph) VII. Engine failure/spinout (30-50 mph)		
TEST ENGINEER C. Stauffer		OPER. IN COMMAND D. Hall		APPROVAL G. Sargent		
TEST PROCEDURE						
Normal start, etc. in accordance with Procedures and Checklists. Proceed to a suitable water test site agreeable to the C.O.R. NOTE: Sea states are critical for the demonstration; SS < 1 is optimum, SS < 2 is acceptable, SS < 3 is limiting. Conduct Acceptance and Type Tests (Ref.: DAAK02-75-C-0149, Exhibit I, Pages 10 and 11). I. Water hover per Attachment I (Ref. Item (9)(a)1)b) - Acceptance II. Speed runs per Attachment II (Ref. Items (9)(a)1)d) - Acceptance III. Cabin noise level per Att. III (Ref. Item (9)(a)5) - Type IV. Maneuvering 8's per Att. IV (Ref. Item (9)(a)1)f) - Type V. Safe limits per Att. V (Ref. Item (9)(a)1)a) - Type VI. Crash stop per Att. VI (Ref. Item (9)(a)1)e) - Type VII. Spin out per Att. VII (Ref. Item (9)(a)1)g) - Type Engine START 0900 Lift off 0910 Depart Azules 0912 (for Ft. St. J) Arrive Ft. St. J 1008 (41 knots average)						

LOCAL FT ST J
70 1100

U.S. ARMY ACCEPTANCE

LACV-30-1

WATER HOVER WITHOUT LOAD

1. Record craft weight 80,000 lbs. 447 l.c.g.
2. In cushion mode, trim and perform a 15 minute hover demonstration into the wind.
3. Manually record the following data:

	<u>Start</u>	<u>Complete</u>
Time	<u>0915</u>	<u>0930</u>
Sea State	<u>21</u>	<u>21</u>
Heading	<u>140</u>	<u>135</u>
Wind/Vel.	<u>4V</u>	<u>4V</u>
% Fuel (Fwd.)	<u>5</u> <u>12.5</u>	<u>5</u> <u>12.5</u>
(Main)	<u>35</u> <u>35</u>	<u>32.5</u> <u>32.5</u>
(Aft)	<u>42.5</u>	<u>42.5</u>
N ₂ (%)	<u>95</u> <u>95</u> <u>95</u> <u>95</u>	<u>95</u> <u>95</u> <u>95</u> <u>95</u>
TOP (psig)	<u>22</u> <u>24</u> <u>24</u> <u>23</u>	<u>23</u> <u>25</u> <u>24</u> <u>23</u>

COMMENTS:

Completed Charles L. Sturges

Accepted Harold S. [Signature]
U.S.A. Representative

Verified U.S. for
BAC Quality

U.S. ARMY ACCEPTANCE

LACV-30-1

OVERWATER SPEED RUNS

1. Proceed to the selected operating area.

2. Record environmental data off cushion.

+30
OAT (°C)

41
Sea State

4/V
W/V

76,000
G.W. (lbs.)

3. Hover into the wind and trim as required.

4. Accelerate thru hump observing engine limits.

5. Continue acceleration to full speed (30 - 50 mph target) with ballast trim as required for maximum performance.

6. Record data at maximum speed (53 mph CAS).

T ₇ (°C)	<u>580</u>	<u>595</u>	<u>590</u>	<u>575</u>
N ₁ (%)	<u>99</u>	<u>100</u>	<u>100</u>	<u>100</u>
N ₂ (%)	<u>95</u>	<u>95</u>	<u>95</u>	<u>95</u>
TOP (psi)	<u>52</u>	<u>51</u>	<u>52</u>	<u>52</u>
Limiting Parameter/Value	<u>#2 EOT 595</u>			

NOTE: Speed obtainable may be a function of Sea State and/or Gross Weight. Maximum permissible speeds, CAS (mph) = IAS - Wind Speed are: SS1 = 60, SS2 = 45, SS3 = 35.

7. If practicable, timed runs should be made in near calm water over a measured course. Upwind and downwind passes should be made if the head/tail wind component is greater than 5 mph. Record pertinent data below:

<u>W/V</u>	<u>Heading</u>	<u>Dist.</u>	<u>Time</u>	<u>Speed</u>
<u>4/V</u>	<u>160</u>	<u>1/4 m</u>	<u>1.12</u> min	<u>53 k</u>
_____	_____	_____	_____	_____

7. Cont'd.

NOTE: If used, record craft data in Item 6.

8. COMMENTS:

DATA Taken by MSgt R. Layman

Completed Chas L. Stuffer Accepted ~~Harold~~
U.S.A. Representative

Verified C. I. S. for
BAC Quality

U.S. ARMY ACCEPTANCE

LACV-30-1

CABIN NOISE LEVEL - FULL SPEED

1. Concurrent with Attachment A1-II, conduct a survey with engines at full power and craft at full speed. Obtain noise data at ear level.

2. Record reference data:

T ₇ (°C)	<u>520</u>	<u>540</u>	<u>545</u>	<u>520</u>
N ₁ (%)	<u>91</u>	<u>94</u>	<u>92</u>	<u>94</u>
N ₂ (%)	<u>93</u>	<u>95</u>	<u>95</u>	<u>95</u>
TOP (psi)	<u>43</u>	<u>45 (corr.)</u>	<u>43</u>	<u>43</u>
<u>5</u> No. of Crew	<u><1</u> SS	<u>+1</u> OAT (°C)	<u>42</u> IAS (mph)	

3. Record Octave Band Analyzer data:

Freq. (hz)	A Operator B		A Passenger B	
	Raw	Corr.	Raw	Corr.
16,000	<u>61</u>	<u>66</u>	<u>62</u>	<u>68</u>
8,000	<u>63</u>	<u>69</u>	<u>60</u>	<u>65</u>
4,000	<u>66</u>	<u>71</u>	<u>68</u>	<u>71</u>
2,000	<u>75</u>	<u>81</u>	<u>77</u>	<u>83</u>
1,000	<u>82</u>	<u>88</u>	<u>83</u>	<u>89</u>
500	<u>84</u>	<u>89</u>	<u>85</u>	<u>90</u>
250	<u>91</u>	<u>94</u>	<u>93</u>	<u>99</u>
125	<u>94</u>	<u>99</u>	<u>96</u>	<u>101</u>

NOTE: A is AT MAX. CONT. Power (Normal)
B is AT MAX. Power (5 minute limit)

4. Record model and S/N of Test Equipment.

OCTAVE Band Noise Analyzer
General Radio Corp Type 1588P S/N 732

5. Attach calibration sheets.

N/A

Completed

Chas L. Stoffer

Accepted

[Signature]
U.S.A. Representative

Verified

C. L. Stoffer
BAC Quality

U.S. ARMY ACCEPTANCE

LACV-30-1

MANEUVERING (8's) - OVER WATER

1. Proceed to the selected operations area.

NOTE: If practicable, maneuvers should be made near buoys so that turning radii can be estimated. Alternately, distances can be measured by radar.

2. Demonstrate maneuvering by performing Figure 8's at two speeds (IAS) as determined in BAC tests to be safe in the existing sea and wind conditions (30 - 50 mph target entry).
3. Record data as follows:

	<u>Pattern 1</u>	<u>Pattern 2</u>
Sea State	<u>51</u>	<u>5</u>
W/V	<u>4/V</u>	<u>4/V</u>
Radii (Up wind)	<u>1500</u>	<u>400</u>
(Down wind)	<u>—</u>	<u>—</u>
Method	<u>Estimated</u>	(Radar, other)
Average N ₂ (%)	<u>95</u>	<u>90</u>
Maximum TOP (psi)	<u>46</u>	<u>42</u>
Entry Speed (IAS)	<u>40</u>	<u>30</u>

4. Comments:

Completed Chris T. Sayer

Accepted August
U.S. A. Representative

Verified A.L. Sayer
BAC Quality

U.S. ARMY ACCEPTANCE

LACV-30-1

SAFE OPERATING LIMITS (WATER)

1. Proceed to the selected operations area.
2. Based on BAC tests under similar water and wind conditions, demonstrate that the craft will not "Plow In" at selected speeds in straight and yawed conditions (over water).
3. Record the following data:

	<u>Yaw Angle = 0</u>	<u>Yaw Angle = 30 (Enter)</u>
Sea State	<u>21</u>	<u>21</u>
W/V	<u>41</u>	<u>41</u>
Av. N ₂ (%)	<u>95</u>	<u>95</u>
Av. TOP (psi)	<u>48</u>	<u>48</u>
Entry Speed (IAS)	<u>45</u>	<u>45</u>

4. Record any adverse behavior.

None


NOTE: "Plow In" is primarily encountered at high speeds over calm water where craft pitch trim is bow down. If requested and practicable, trim ballast may be moved forward to a condition proven safe in BAC tests for the foregoing demonstration.

5. Record fuel quantities (%) demonstrated:

Forward	<u>0</u>	<u>0</u>
Main	<u>12</u>	<u>15</u>
Aft	<u>30</u>	<u>—</u>

6. Comments:

Completed Chris J. Stauffer

Accepted 
U.S. A. Representative

Verified A. J. Stauffer
BAC Quality

U.S. ARMY ACCEPTANCE

LACV-30-1

ENGINES (2) FAILURE - "CRASH STOP"

1. Proceed to the selected operations area.
2. Based on BAC tests under similar water and wind conditions, demonstrate the craft under simulated engines (2) failure conditions with optimum trim from a target speed of 30-50 mph.
3. Record pertinent data.

	<u>Yaw Angle = 0</u>	<u>Yaw Angle = 30</u> (Enter)
Sea State	<u>21</u>	<u>21</u>
W/V	<u>44</u>	<u>44</u>
"Cut" IAS	<u>40</u>	<u>45</u>
Time to Stop	<u>9</u>	<u>15</u>
Entry N2 (%)	<u>95</u> Av.	<u>95</u> Av.
Entry TOP (psi)	<u>44</u> Av.	<u>48</u> Av.

4. Record craft behavior.

No adverse behavior

5. Record fuel quantities (%) demonstrated:

Forward	<u>0</u>	<u>0</u>
Main	<u>20</u>	<u>20</u>
Aft	<u>30</u>	<u>—</u>

6. Comments:

Stop in 9 sec; estimated 50 yds.

Completed Chick T. Staff Accepted [Signature]
U.S.A. Representative

Verified C. T. Staff
BAC Quality

U.S. ARMY ACCEPTANCE

LACV-30-1

ENGINE (1) FAILURE - "SPINOUT"

1. Proceed to the selected operations area.
2. Based on BAC tests under similar water and wind conditions, demonstrate the craft under simulated engine (1) failure conditions with optimum trim from a target speed of 30-50 mph. Selected engine to be cut is at operator's discretion; corrective action is allowable.

3. Record pertinent data:

	<u>Yaw Angle = 0</u>	<u>Yaw Angle = 30</u> (Enter)
Sea State	<u>21</u>	<u>21</u>
W/V	<u>40</u>	<u>40</u>
"Cut" IAS	<u>40</u>	<u>30</u>
Entry N ₂ (%)	<u>95</u> Av.	<u>95</u> Av.
Entry TOP (psi)	<u>48</u> Av.	<u>44</u> Av.

4. Record corrective action.

Reduced power on opposite side

5. Record craft behavior.

*YAW in direction of cut, side slip
UNTIL corrective action is taken.
Estimate roll angle to failure = 25°.*

6. Record fuel quantities (%) demonstrated.

Forward

0

0

Main

20

20

Aft

30

7. Comments:

Completed

Charles J. Shaffer

Accepted

[Signature]
U.S.A. Representative

Verified

C. J. Shaffer
BAC Quality

BELL AEROSPACE ACV TEST PLAN		TYPE LACV-30-1		OPER. NO. A2- 0113 (1977)	
ACV CREW		NO CHASE AIRCRAFT		TEST CONDITIONS	
CREW POSITION	NAME	TYPE A/C	CREW		
Operator	D. Hall			WEIGHT	
Oper. Nav.	R. Layman			FUEL	As Noted
Obs./MERAD	L.T. R. Lindsey			C.G.	See Loading Sheet
Obs./PICARE	G. PENN	INSTRUMENTATION PLAN NONE		BALLAST	574 447 40,000
Obs./C.O.R.	J. Sargent	SETUP NO. N/A	AMEND NO. N/A	ALT SETTING	30.09
		RADIO FREQ.		PRESS ALT	5.L.
TEST ENGINEER	C. Stauffer	URC-80	VRC-46	WIND	270/12
TEST DIRECTOR	C. Stauffer	P 16	P	TEMP	+25°F
FINAL GO-NO GO AUTHORITY	C. Stauffer	S 8	S	Sea State	1
CRAFT CHANGES SINCE LAST OPERATION				TEST PURPOSE	
Delivery Configuration Less: 1. EGT. Wiring, BTBD Power Wires 2. Windshield Washer Inoperative 3. PAT Nav. Light Out F m A Fuel: P 20 62.5 42.5 S 25 62.5 42.5				I. Water hover with full load (115,000 lb. G.W.) for 15 minutes.	
TEST ENGINEER C. Stauffer		OPER. IN COMMAND D. Hall		APPROVAL	
TEST PROCEDURE					
Normal start, etc. in accordance with Procedures and Checklists. Proceed to a suitable water test site agreeable to C.O.R. Conduct Acceptance Test (Ref: DAAK02-75-C-0149, Exhibit I, Page 11). I. Water hover per Att. I (Ref. Item (9)(a)b). Engine Start - 1140 Lift off - 1147 on 1/13/77 Notes: 1. P.S. 3+4 Fine out on rapid power reduction. 2. P.S. 4 repeated at shore departure. Res. 7 min. 3. P.S. 4 No Ng Control 3/D 1218 To T/5 P.S. 4. L.O. - 1336 on 1/13/77					

U.S. ARMY ACCEPTANCE

LACV-30-1

WATER HOVER WITH LOAD

1. Record craft weight 116,000 lbs. 445 l.c.g.
2. In cushion mode, trim and perform a 15 minute hover demonstration into the wind.
3. Manually record the following data:

	<u>Start</u>		<u>Complete</u>	
Time	<u>1350</u>		<u>1405</u>	
Sea State	<u><1</u>		<u><1</u>	
Heading	<u>330</u>		<u>330</u>	
Wind/Vel.	<u>140/10</u>		<u>140/10</u>	
% Fuel (Fwd.)	<u>20</u>	<u>25</u>	<u>10</u>	<u>10</u>
(Main)	<u>62.5</u>	<u>62.5</u>	<u>50</u>	<u>50</u>
(Aft)	<u>42.5</u>		<u>70</u>	
N ₂ (%)	<u>94</u>	<u>94</u>	<u>94</u>	<u>94</u>
TOP (psig)	<u>48</u>	<u>49</u>	<u>47</u>	<u>47</u>

COMMENTS:

*Also speed runs; average with Max
Cush Power 33 mph. R. Lagman using radar
Target distance/Time.*

Completed C. L. Shuff

Accepted [Signature]
U.S.A. Representative

Verified C. L. Shuff
BAC Quality

NOTE: May not be required since hover overland conducted at 115,000 G.W.

TABLE 4.3 LACV-30-2 AT BAT

THIS TABLE CONSISTS OF A SERIES OF TEST PLANS
FOLLOWED BY TEST DATA.

BELL AEROSPACE ACV TEST PLAN		TYPE LACV-30-2		OPER. NO. A1-0409	
ACV CREW		NO CHASE AIRCRAFT		TEST CONDITIONS	
CREW POSITION	NAME	TYPE A/C	CREW		TAKEOFF
Operator	D. Hall			WEIGHT	Loading 006-2
Co-Operator	G. Yaeger			FUEL	(attached)
U.S.A. Obs.	J. Sargent			C.G.	
		INSTRUMENTATION PLAN #1		BALLAST	
		SETUP NO.	AMEND NO.	ALT SETTING	
		RADIO FREQ.		PRESS ALT	
TEST ENGINEER	C. Stauffer	UHF	121.7	WIND	
TEST DIRECTOR	"	UHF-FM	6	TEMP	
FINAL GO-NO GO AUTHORITY	"	VHF-FM	TBD		
CRAFT CHANGES SINCE LAST OPERATION				TEST PURPOSE	
				A. Demonstration to U.S. Army for acceptance: <ol style="list-style-type: none"> 1. Hover with full load. 2. System run-in tests 3. Cabin noise level (stationary) 	
TEST ENGINEER <i>C. Stauffer</i>		OPER. IN COMMAND <i>D. Hall</i>		APPROVAL <i>Jul 3 Sargent</i>	
TEST PROCEDURE					
I. Position craft on BAC concrete ramp north of production hangar. Restrain as required for wind and slope. II. Perform Operator Inspection IAW Checklist. III. Perform normal pre-start, start, etc. IAW Checklists. IV. Raise craft in hover mode. <ol style="list-style-type: none"> A. Conduct acceptance tests (DAAK02-75-C-0149, Attachment 1, Pages 10 and 11). <ol style="list-style-type: none"> 1. Hover with full load per Attachment I (Ref. Item 9(A)2)A. 2. Perform system run-in tests per Attachment 2 (Ref. Item 9(A)3)A & B. 3. Obtain cabin noise level data per Attachment 3 (Ref. Item 9(A)5). 					

U.S. ARMY ACCEPTANCE

LACV-30-2

LAND HOVER WITH LOAD

1. Verify craft configured per Loading.
2. In mushion mode, trim and perform a 15 minute demonstration at N₂ maximum (91% N₂ minimum).
3. Manually record the following data:

	<u>START</u>	<u>COMPLETE</u>
Time	<u>1440</u>	<u>1455</u>
Fuel (FWD)	(P) <u>60</u> (S) <u>63</u>	_____
(Main)	<u>60</u> <u>65</u>	_____
(Aft)	<u>25</u>	_____
T ₇ (°C)	<u>570</u> <u>540</u> <u>480</u> <u>460</u>	_____
N ₁ (%)	<u>93.0</u> <u>93.5</u> <u>89.5</u> <u>88.5</u>	_____
N ₂ (%)	<u>91</u> <u>91</u> <u>91</u> <u>91.5</u>	_____
Torque (psi)	<u>27</u> <u>27</u> <u>20</u> <u>20</u>	_____

COMMENTS:

COMPLETED

[Signature]
BAC

ACCEPTED

[Signature]
U.S.A. REPRESENTATIVE

VERIFIED

[Signature] 4/9/70
BAC QUALITY

U.S. ARMY ACCEPTANCE

LACV-30-2

SYSTEM RUN-IN TESTS

1. Starting concurrent with Hover (Attachment 1) and continuing off cushion for a total of one hour, functionally operate the following systems:

Start Time	<u>1445</u>	Complete Time	<u>1545</u>
Puff Ports (20 cycles each)	<u>YES</u>	<u>S</u>	
Cabin Heaters (Both, Lo and Hi)	<u>YES</u>		
Windshield Heat (Continuous)	<u>YES</u>		
Air Conditioner (Vent & Cool)	<u>YES</u>		
APU (Generator On)	<u>YES</u>		
AN/URC-80 (4 Contacts)	<u>YES</u>		
AN/URC-46 (4 Contacts)	<u>NO</u>		
AN/PRC-94 (4 Contacts)	<u>YES</u>		
RMHS System (Continuous)	<u>YES</u>		
AN/ASN-43 Compass (Continuous)	<u>NO</u>		
Radar (Continuous)	<u>YES</u>		
Fuel Trim (To/From Transfers)	<u>YES</u>		
Engines (Continuous)	<u>YES</u>		
Propellers (As Required)	<u>YES</u>		
Windshield Wipers (4 Cycles)	<u>YES</u>		
Spotlight (4 Cycles)	<u>YES</u>		
Running Lights (Continuous)	<u>YES</u>		
Horn (4 Blasts)	<u>YES</u>		
	BAC	U.S.A.	

DISCREPANCIES AND DISPOSITION:

COMPLETED

J. H. Heger
BAC

ACCEPTED

J. H. Heger
U.S.A. REPRESENTATIVE

VERIFIED

Ed Muller 4/9/76
BAC QUALITY

U.S. ARMY ACCEPTANCE

LACV-30-2

CABIN NOISE LEVEL - STATIONARY

1. Concurrent with Attachment 1, conduct survey with engines at full power (N₂ maximum). Using an Octave-Band Noise Analyzer, record noise levels at ear level.

	<u>Operator</u>		<u>Freq.</u>	<u>Passenger</u>	
	(Raw)	(Corr.)	(Hertz)	(Raw)	(Corr.)
Band 1	<u>0</u>	<u> </u>	16000	<u>0</u>	<u> </u>
2	<u>58</u>	<u> </u>	8000	<u>58</u>	<u> </u>
3	<u>64</u>	<u> </u>	4000	<u>64</u>	<u> </u>
4	<u>66</u>	<u> </u>	2000	<u>68</u>	<u> </u>
5	<u>74</u>	<u> </u>	1000	<u>78</u>	<u> </u>
6	<u>84</u>	<u> </u>	500	<u>88</u>	<u> </u>
7	<u>98</u>	<u> </u>	250	<u>98</u>	<u> </u>
8	<u>102</u>	<u> </u>	125	<u>106</u>	<u> </u>

Record engine parameters.

N ₁ (%)	<u>93.0</u>	<u>93.5</u>	<u>89.5</u>	<u>88.5</u>
N ₂ (%)	<u>91.0</u>	<u>91.0</u>	<u>91.0</u>	<u>91.5</u>
Torque (psi)	<u>27</u>	<u>27</u>	<u>20</u>	<u>20</u>
Prop. Pitch	<u>0</u>		<u>0</u>	

Record Model and Serial No. of Test Equipment.

General Radio Model 1558AP Octave Band Noise Analyzer, S/N 732.

Attach Calibration Sheets.

COMPLETED

[Signature]
BAC

ACCEPTED

[Signature]
U.S.A. REPRESENTATIVE

VERIFIED

Paul Mueller 4/9/76
BAC QUALITY

LACV-30 #2, VOYAGEUR #006
2ND TEST WEIGHT AND BALANCE

	Weight	Longitudinal Arm	Moment
Basic Weight LACV-30 #2 Voyageur	51859	488.4	25328000
#006 From LACV-30 #1 Actual Weight			
Test Instrumentation	(536)		(322906)
Instr. Package Install. Craft	34	439.5	14943
Attitude			
Instr. Package Install. Data	484	613.8	297079
Acquisition			
Flex. Conduit for above	10	690.0	6900
Control Install. Cabin Data	8	498.0	3984
Acquisition			
Revised Basic Weight	52395	489.6	25650906
Load Spreaders - Fwd	1106	299	330694
Load Spreaders - Aft	958	483	462714
Lashings - MILVAN - Fwd	428	390	166920
Tee Hooks	152	658	100016
Sub-Total Weight	55039	485.2	26711250
Crew	360	653	235080
Passengers	360	716	257760
Unusable Fuel	650	397.5	258375
Carbo - MILVAN #3610	4745	390	1850550
- Ballast	14331	390	5589090
Operating Weight	75485	462.4	34902105
Fuel - Fwd 73% (5103)	3748	100.5	376674
- Main 85% (14755)	12543	397.5	4985843
- Aft 12% (4849)	590	810.5	478195
Gross Weight	92366	441.1	40742817

BELL AEROSPACE ACV TEST PLAN		TYPE LACV-30-2		OPER. NO. A2-0409	
ACV CREW		NO CHASE AIRCRAFT		TEST CONDITIONS	
CREW POSITION	NAME	TYPE A/C	CREW		
Operator	Hall			WEIGHT	Loading 006-2
Co-Operator	Yaeger			FUEL	(Attached)
U.S.A. Obs.				C.G.	
		INSTRUMENTATION PLAN #1		BALLAST	
		SETUP NO.	AMEND NO.	ALT SETTING	
		RADIO FREQ.		PRESS ALT	
TEST ENGINEER	Stauffer	VHF	121.7	WIND	
TEST DIRECTOR	"	VHF-FM	P 55.85 S 85.55	TEMP	
FINAL GO-NO GO AUTHORITY	"	UHF-FM	6		
CRAFT CHANGES SINCE LAST OPERATION				TEST PURPOSE	
				A. Demonstration to U.S. Army for acceptance: 1. Hover with no load. 2. Speed Run (25 - 35 mph)	
TEST ENGINEER <i>C Stauffer</i>		OPER. IN COMMAND <i>D Hall</i>		APPROVAL <i>John B Sargent</i>	
TEST PROCEDURE					
I. Position craft on BAC concrete ramp north of Production Hangar. Restrain as required for wind and slope. II. Perform Operator Inspection IAW Checklist. III. Perform normal pre-start, start, etc. IAW Checklists. IV. Operate craft and systems as required: A. Conduct acceptance tests (DAAK02-75-C-0149, Attachment I, Page 11): 1. Hover without load per Attachment 1 (Ref. Item (9)(a)2)a). 2. Perform speed runs per Attachment 2 (Ref. Item (9)(a)2)b). V. Return to BAC Ramp and secure craft.					

U.S. ARMY ACCEPTANCE

LACV-30-2

OVERLAND HOVER WITHOUT LOAD

1. Verify craft configured per loading.
2. In cushion mode, trim and perform a 15 minute demonstration at N₂ maximum (91% N₂ minimum).
3. Manually record the following data:

	<u>START</u>	<u>COMPLETE</u>
Time	_____	_____
Fuel (Fwd)	_____	_____
(Main)	<u>SEE A1</u>	_____
(Aft)	_____	_____
T7 (°C)	_____	_____
N ₁ (%)	_____	_____
N ₂ (%)	_____	_____
Q (psi)	_____	_____

COMMENTS:

Mr. Sargent was satisfied with previous results; therefore repeat of test was not necessary.

*D. F. Shuler
4/9/76*

COMPLETED

[Signature]
BAC

ACCEPTED

[Signature]
U.S.A. REPRESENTATIVE

VERIFIED

[Signature] 4/9/76
QUALITY

BEST AVAILABLE COPY

U.S. ARMY ACCEPTANCE

LACV-30-2

OVERLAND SPEED RUNS (25 TO 35 mph)

1. Determine wind direction in the Test Area.
2. Record Wind Direction 345, Velocity 10 mph.
3. On wind dependent course selected, perform two reciprocal runs at speed from 25 to 35 mph (estimated).
4. Record IAS, ground speeds attained and measurement method (pacer, time/dist., other).

	<u>IAS (mph)</u>	<u>GS (mph)</u>	<u>Method (Time/Dist)</u>
Run 1	<u>35</u>	<u>30</u>	<u>SCALED EAST TO WEST</u>
Run 2	<u>55</u>	<u>12</u>	<u>SCALED WEST TO EAST</u>
Average	<u>45</u>	<u>36</u>	<u>SCALED (AVERAGE)</u>

5. COMMENTS:

COMPLETED

BAC

ACCEPTED

U.S.A. REPRESENTATIVE

VERIFIED

BAC QUALITY

TABLE 4.4. LACV-30-2 AT APG

THIS TABLE CONSISTS OF A SERIES OF TEST PLANS
FOLLOWED BY TEST DATA.

BELL AEROSPACE ACV TEST PLAN				TYPE LACV-30-2	OPER. NO. A1-0914	
ACV CREW		NO CHASE AIRCRAFT		TEST CONDITIONS		
CREW POSITION	NAME	TYPE A/C	CREW		TAKEOFF	LAND
Operator	D. Hall			WEIGHT	75,000#	73,000
Oper. Nav.	C. Stauffer			FUEL	See A1-1	
Obs 1	Capt Penick			C.G.	433	
Obs 2	F. Weller	INSTRUMENTATION PLAN APG		BALLAST	As Required	
Obs./C.O.R.	J. Sargent	SETUP NO.	AMEND NO.	ALT SETTING	0	
		RADIO FREQ.		PRESS-ALT BAC	30'34" hg	
TEST ENGINEER	C. Stauffer	URC-80	VRC-46	WIND	18k/2	
TEST DIRECTOR	C. Stauffer	P	P	TEMP	30.40c 31.0c	
FINAL GO-NO GO AUTHORITY	C. Stauffer	S	S	Sea State	1A/4	
CRAFT CHANGES SINCE LAST OPERATION AMS Complete Two MILVANS				TEST PURPOSE I. Water hover (15 minutes) II. Speed runs (30-50 mph) III. Obstacles (wall & ditch) IV. Net Thrust Measurements V. Air Conditioning Functional Test		
TEST ENGINEER C. Stauffer		OPER. IN COMMAND D. Hall		APPROVAL C. Stauffer		
TEST PROCEDURE						
<p>Normal start, etc. in accordance with Procedures and Checklists. Proceed to a suitable water test site agreeable to the C.O.R.</p> <p>NOTE: Sea states are critical for the demonstration; SS < 1 is optimum, SS < 2 is acceptable, SS < 3 is limiting.</p> <p>Conduct Acceptance and Type Tests (Ref.: DAAK02-75-C-0149, Exhibit I, Pages 10 and 11).</p> <p>I. Water hover per Attachment I (Ref. Item (9)(a)1)b) - Acceptance)</p> <p>II. Speed runs per Attachment II (Ref. Items (9)(a)1)d) - Acceptance)</p> <p>III. Obstacles per Attachment III (Ref. Item (9)(a)2)d) - Type)</p> <p>IV. Net thrust per Attachment IV (Ref. Item (9)(a)1)c) - Type)</p> <p>V. Air conditioning per Attachment V (Ref. Item (9)(b)7) - Acceptance)</p>						

U.S. ARMY ACCEPTANCE

LACV-30-2

WATER HOVER WITHOUT LOAD

1. Record craft weight 75,000 lbs. 433 l.c.g.
2. In cushion mode, trim and perform a 15 minute hover demonstration into the wind.
3. Manually record the following data:

	<u>Start</u>				<u>Complete</u>			
Time	<u>1450</u>				<u>1510</u>			
Sea State	<u>Calm</u>				<u>Calm</u>			
Heading	<u>115</u>				<u>120</u>			
Wind/Vel.	<u>L/V</u>				<u>L/V</u>			
% Fuel (Fwd.)	<u>85</u>	<u>85</u>			<u>85</u>	<u>85</u>		
(Main)	<u>30</u>	<u>25</u>			<u>30</u>	<u>25</u>		
(Aft)	<u>0</u>				<u>0</u>			
N ₂ (%)	<u>82</u>	<u>81</u>	<u>82</u>	<u>82</u>	<u>82</u>	<u>82</u>	<u>81</u>	<u>82</u>
TOP (psig)	<u>14</u>	<u>16</u>	<u>14</u>	<u>16</u>	<u>15</u>	<u>16</u>	<u>15</u>	<u>16</u>

COMMENTS:

NONE

Completed

C. F. Stuffer

Verified

Paul Mueller

BAC Quality

Accepted

3. Sargent

U.S.A. Representative

BEST AVAILABLE COPY

U.S. ARMY ACCEPTANCE

LACV-30-2

OVERWATER SPEED RUNS

1. Proceed to the selected operating area.
2. Record environmental data off cushion.

30.4 Calm 180/2 25,000
OAT (°C) Sea State W/W G.W. (lbs.)

3. Hover into the wind and trim as required.
4. Accelerate thru hump observing engine limits. 34 sec.
5. Continue acceleration to full speed (30 - 50 mph target). with ballast trim as required for maximum performance.

6. Record data at maximum speed (45 mph CAS). 45 mph N
45 mph P/W

T ₇ (°C)	<u>590</u>	<u>586</u>	<u>600</u>	<u>580</u>
N ₁ (%)	<u>98</u>	<u>99.5</u>	<u>95</u>	<u>95.5</u>
N ₂ (%)	<u>90</u>	<u>90</u>	<u>90</u>	<u>90</u>
TOP (psi)	<u>40</u>	<u>42</u>	<u>36</u>	<u>36</u>
Limiting Parameter/Value	<u>Trim Attitude</u>			

NOTE: Speed obtainable may be a function of Sea State and/or Gross Weight. Maximum permissible speeds, CAS (mph) = IAS - Wind Speed are: SS1 = 60, SS2 = 45, SS3 = 35.

7. If practicable, timed runs should be made in near calm water over a measured course. Upwind and downwind passes should be made if the head/tail wind component is greater than 5 mph. Record pertinent data below:

<u>W/V</u>	<u>Heading</u>	<u>Dist.</u>	<u>Time</u>	<u>Speed</u>
<u>L/V</u>	<u>245</u>	<u>2 n.m.</u>	<u>3.2</u>	<u>38.4 (44 mph)</u>
<u>L/V</u>	<u>060</u>	<u>2 n.m.</u>	<u>3.4</u>	<u>35.5 (41 mph)</u>

7. Cont'd.

NOTE: If used, record craft data in Item 6.

8. COMMENTS:

1. Item 7, 2nd run had gentle placid prior to completion.

2. Speed runs were not at maximum power due to overcompensated by limits.

Completed

C. L. Staffer

Accepted

John F. Sargent
U.S.A. Representative

Verified

Paul Mueller
BAC Quality

BEST AVAILABLE COPY

US ARMY ACCEPTANCE
LACV-30-2

OBSTACLES

1. Record craft weight 78,000 lbs and 438.0 l.c.g.
2. With N₂ at maximum and power as required, negotiate a ditch (approximately 6 ft wide by 9 ft deep) and vertical obstacle (3 ft maximum height).
3. Manually record the following data:

	<u>DITCH</u>				<u>STEP</u>			
TIME	9/14/76 1530				9/15/76 1345			
HEADING	180				360			
WIND/VEL	4V				090/1			
N ₁ (%)	98	98	98	98	100	99	100	100
N ₂ (%)	90	90	90	90	100	95	95	84
T ₇ (°C)	600	600	600	600	630	630	630	630
TOP (psig)	42	42	41	40	38	48	48	48

COMMENTS:

IAS 22 mph
Engine Readings
Are Approximate

IAS 33 mph
Engine Readings
Are Approximate

COMPLETED Chick L. Smith

ACCEPTED

John S. Sargent
US Army Representative

VERIFIED

Frank Mueller
BAT QUALITY

NOTE: Measured 10 foot wide ditch at
crossing point.

Total Time for Operations = 1.0 hrs.

BEST AVAILABLE COPY

US ARMY ACCEPTANCE
LACV-30-2

NET THRUST MEASUREMENT

1. Record craft weight 78,600 lbs and 440 l.c.g.
2. On water, tether the craft to a government furnished thrust measuring device using a bridle attached to bow (and stern) tow fittings.
3. At target shaft speeds (N_2) of 60 and 95%, measure reverse and forward thrust. Record data in attached sheet (Test Nos. A thru D).

COMMENTS:

Due to inability to maintain draft
nominal to target point, the values
obtained are not considered to be
the maximum available. Test will
be repeated over. and o/p 9/16/56

COMPLETED

Chas. J. Sargent

VERIFIED

Jack Mueller

BAT QUALITY

ACCEPTED

John J. Sargent
US Army Representative

BEST AVAILABLE COPY

BEST AVAILABLE COPY

9/13/76

TEST DATA RECORDING LOG						OPERATION NO. A1-IV	SHT 2 OF 2
TEST NO.	INST	POWER PLANT				REMARKS	
		1	2	3	4		
A	T7					Reverse thrust off cushion Target = 60% Measured thrust = 540 lbs	
	N1						
	N2						
	TOP						
	PP	-23.5		-23.5			
		W/V	ASI RDG	HEADING			
B	T7					Reverse thrust on cushion Target = 95% Measured thrust = 220 lbs	
	N1						
	N2						
	TOP						
	PP	-23.5		-23.5			
		W/V	ASI RDG	HEADING			
C	T7					Forward thrust off cushion Target = 60% Measured thrust = 2300 lbs	
	N1						
	N2						
	TOP						
	PP	+23.5		+23.5			
		W/V	ASI RDG	HEADING			
D	T7					Forward thrust on cushion Target = 95% Measure thrust = 3700 lbs	
	N1						
	N2						
	TOP						
	PP	+23.5		+23.5			
		W/V	ASI RDG	HEADING			
	T7					<div style="display: flex; justify-content: space-between;"> <div> 10/10 180/2 Hdg 230 START TIME 1115 TEMPERATURE 15.6°C BAROMETER 30.13 SEA STATE C/M </div> <div> STOP 1210 16.0° 30.13 20/M </div> </div>	
	N1						
	N2						
	TOP						
	PP						
		W/V	ASI RDG	HEADING			

US ARMY ACCEPTANCE
LACV-30-2

AIR CONDITIONER PERFORMANCE

1. In conjunction with any previous tests, determine the performance of the air conditioner (Target: 85°F maximum effective temperature at outside temperature of 125°F).

2. Manually record the following data (30 minute period):

	<u>START</u>	<u>STOP</u>
TIME (AIR CONDITIONER)	<u>1425</u>	<u>1455</u>
OUTSIDE AIR TEMPERATURE	<u>101°F</u>	<u>101°F</u>
CABIN TEMPERATURE:		
LEFT FRONT	<u>101</u>	<u>78</u>
RIGHT FRONT	<u>101</u>	<u>78</u>
LEFT REAR	<u>101</u>	<u>78</u>
RIGHT REAR	<u>101</u>	<u>78</u>
AVERAGE	<u>101</u>	<u>78</u>

COMMENTS:

Thermometer on Air Conditioner
cooled in 10 minutes to 42°F.

COMPLETED	<u>Chris L. Stoff</u>	ACCEPTED	<u>John 3. Sargent</u>
VERIFIED	<u>Fred Muller</u>		
	BAT QUALITY		

BEST AVAILABLE COPY

BEST AVAILABLE COPY

BELL AEROSPACE ACV TEST PLAN		TYPE LACV-30-2		OPER. NO. S - 0916	
ACV CREW		CHASE AIRCRAFT		TEST CONDITIONS	
CREW POSITION	NAME	TYPE A/C	CREW	WEIGHT	TAKEOFF
OPERATOR	D. Hall				N/A
				FUEL	
				C.G.	
		INSTRUMENTATION PLAN APC		BALLAST	
		SETUP NO. A	AMEND NO. 2	ALT SETTING	
		RADIO FREQ.		PRESS ALT	
TEST ENGINEER	C. Bardek	N/A		WIND	
TEST DIRECTOR	C. Bardek			TEMP	
FINAL GO-NO GO AUTHORITY	C. Stauffer				
CRAFT CHANGES SINCE LAST OPERATION				TEST PURPOSE	
1. Loaded MILVANS replaced with Empty 2. Instrumentation patched as noted				1. Overland Thrust Measurement 2. Partial Propeller Gearbox Vibration Survey 3. Exhaust Collector Vibration Survey	
NOTE: Exhaust Collectors not installed					
TEST ENGINEER		OPER. IN COMMAND		APPROVAL	
				C. L. Stauffer	
TEST PROCEDURE					
A. Tether CRAFT AT STEIN TO CFE Thrust Measurement Yaw. Attach bridle on STBD side to restrain lateral movement B. Perform normal pre-operational, START, etc. procedures C. With Prop Control set for 0 effective thrust, step up N ₂ from minimum to maximum in 2-3% increments. Voice Annotate magnetic Tape. D. Set N ₂ at 95%. Advance β for TOP sets of approximately 5% to limit conditions. Manually record DATA on attached sheets. E. AT MAP, reduce N ₂ in 2-3% increments to minimum. Voice Annotate magnetic Tape. F. Secure operations. Record Ambient DATA.					

TEST DATA RECORDING LOG						OPERATION NO. <u>5</u>	SHT <u>1</u> OF <u>2</u>
TEST NO.	INST	POWER PLANT				REMARKS	
		1	2	3	4		
	T7	510	490	500	490	All with N ₂ ≈ 95% Set 0 Effective Thrust	
	N1	87.8	90	87.5	87.2		
	N2	95.5	95.2	95.5	95.3		
	TOP	22	23	22	22		
	PP	≈ 3.50					
	W/V	ASI RDG		HEADING			
	T7	510	520	520	510	Target 25% TOP	
	N1	90.5	91.5	89	89.2		
	N2	95	94.5	95	94.8		
	TOP	25	26	25	25		
	PP	A.S. 2.20					
	W/V	ASI RDG		HEADING			
	T7	520	520	550	530	Target 30% TOP	
	N1	92.3	93.7	91.2	91.4		
	N2	94.3	94	94.3	94		
	TOP	30	30	30	30		
	PP	A.S. 2.40					
	W/V	ASI RDG		HEADING			
	T7	550	540	570	560	Target 35% TOP	
	N1	94.8	96	93.4	93.4		
	N2	93.5	93.2	93.7	93.3		
	TOP	35	36	35	35		
	PP	A.S. 2.40					
	W/V	ASI RDG		HEADING			
	T7	570	550	600	580	Target 40% TOP	
	N1	96	97	96	96		
	N2	93	92.8	95	93.5		
	TOP	40	40	40	40		
	PP	A.S. 2.40					
	W/V	ASI RDG		HEADING			

BEST AVAILABLE COPY

TEST DATA RECORDING LOG						OPERATION NO.	SHT ____ OF ____
TEST NO.	INST	POWER PLANT				REMARKS	
		1	2	3	4		
8500	T7	600	580	640	610	Target 45% TOP	
	N1	98.5	99.8	98.5	98.5		
	N2	92.3	92	92	91.7		
	TOP	45	46	45	46		
	PP	As Req					
	W/V	ASI RDG		HEADING			
	T7	625	610	640	640	To limit power conditions As measured on Shutdown	
	N1	100	101.5	98.5	99		
	N2	81	80	78.5	77.5		
	TOP	53.5	53.5	53.5	53.5		
	PP	+ 23.5		+ 23.5			
	W/V	ASI RDG		HEADING			
	T7					As Req.	
	N1						
	N2						
	TOP						
	PP						
	W/V	ASI RDG		HEADING			
	T7						
	N1						
	N2						
	TOP						
	PP						
	W/V	ASI RDG		HEADING			
	T7						
	N1						
	N2						
	TOP						
	PP						
	W/V	ASI RDG		HEADING			

$$Q: -0.037 \text{ V}$$

4 = 12.07 V = 10890 IB = 5162.7 μ A/WAT
3 = 11.03 = 5450 IB = 5107.5 μ A/WAT

TEST DATA
(SOP HP 70-6)

TEST DATA

(SOP MP 70-6)

Aug 5/55, 2 1 1/2 out

DATE: 16.8.76

SHEET NO.

LACU-30 TONARO PULL
ON LAND

	Force	Time	Rate	Pull
				16
	25 PSI	1355	0.445	2480
			0.465	2580
			0.455	2530
	30 PSI		0.677	3670
			0.695	3710
			0.663	3600
	35 PSI		0.800	4610
			0.807	4540
			0.863	4430
	40 PSI	1000	1.00	5330
			1.02	5430
	45 PSI		1.12	5940
			1.13	6000
			1.14	6040
	MAX PRESS		1.15	6100
			1.18	6250
				6330
	MAX POWER		1.04	5530
				MAX ON OSCILLOSCOPE

STRAP-MT FORM 247, 1 May 74 (Edition of 29 Aug 69 may be used.)

BELL AEROSPACE ACV TEST PLAN		TYPE LACV-30-2		OPER. NO. A2-	
ACV CREW		NO CHASE AIRCRAFT		TEST CONDITIONS	
CREW POSITION	NAME	TYPE A/C	CREW		TAKEOFF
Operator	D. Hall			WEIGHT	115,000
Oper. Nav.				FUEL A 100	F 78 M 54
				C.G.	439.5
		INSTRUMENTATION PLAN APG		BALLAST	50,000 MILWAU STA 273 + 157
Obs./C.O.R.		SETUP NO.	AMEND NO.	ALT SETTING	0
		RADIO FREQ.		PRESS ALT	DA.0 30.16" Hg
TEST ENGINEER	C. Stauffer	URC-80	VRC-46	WIND	030/4
TEST DIRECTOR	C. Stauffer	P	P	TEMP	23.7°C
FINAL GO-NO GO AUTHORITY	C. Stauffer	S	S	Sea State	< 1'
CRAFT CHANGES SINCE LAST OPERATION				TEST PURPOSE	
				I. Water hover with full load (115,000 lb. G.W.) for 15 minutes.	
TEST ENGINEER	OPER. IN COMMAND	APPROVAL			
<i>C. Stauffer</i>	<i>D. Hall</i>	<i>[Signature]</i>			
TEST PROCEDURE					
Normal start, etc. in accordance with Procedures and Checklists. Proceed to a suitable water test site agreeable to C.O.R.					
Conduct Acceptance Test (Ref: DAAK02-75-C-0149, Exhibit I, Page 11).					
I. Water hover per Att. I (Ref. Item (9)(a)b).					
NOTE: Open items from Test A1 may be added by reference to this operation.					

BEST AVAILABLE COPY

BEST AVAILABLE COPY

U.S. ARMY ACCEPTANCE

LACV-30-1

WATER HOVER WITH LOAD

1. Record craft weight 115,000 lbs. 439.5 l.c.g.
2. In cushion mode, trim and perform a 15 minute hover demonstration into the wind.
3. Manually record the following data:

	Start				Complete			
Time	<u>1521</u>				<u>1609</u>			
Sea State	<u>21</u>				<u>21</u>			
Heading	<u>295</u>				<u>292</u>			
Wind/Vel.	<u>030/4</u>				<u>030/4</u>			
% Fuel (Fwd.)	<u>40</u>	<u>40</u>	<u>40</u>	<u>40</u>	<u>40</u>	<u>40</u>	<u>40</u>	<u>40</u>
(Main)	<u>60</u>	<u>60</u>	<u>60</u>	<u>60</u>	<u>60</u>	<u>47</u>	<u>47</u>	<u>47</u>
(Aft)	<u>97</u>	<u>97</u>	<u>97</u>	<u>97</u>	<u>90</u>	<u>90</u>	<u>90</u>	<u>90</u>
N ₂ (%)	<u>92</u>	<u>93</u>	<u>94</u>	<u>93</u>	<u>82</u>	<u>86</u>	<u>87</u>	<u>86</u>
TOP (psig)	<u>42</u>	<u>42</u>	<u>42</u>	<u>42</u>	<u>17</u>	<u>16</u>	<u>18</u>	<u>16</u>

COMMENTS:

OVERCART @ 1521
 6000 101N, 9000 D₂, 42 TOP 2AS 15 mph 1010 water
 WATER 40' at 1500
 Time 100 ^{1.5 min} 1.47 sec = 19.2 mph

Completed

C. L. Stuffs

Accepted

R. J. Sargent
 U.S.A. Representative

Verified

C. E. Brown
 SAC Quality

TABLE 4.5 - THRUST LOADING

Condition	H.P. TOT	H.P. L	H.P. P	C _p	Net Force/Prop lbs.	Aero Drag lbs.	Mon. Drag	Thrust lbs.	C _T	C _T Pred.	η Pred.
Hover Test Point											
1	734	547	184	0.0206	0	19.9	45.4	32.7	0.0020	NA	-
2	828	536	286	0.0325	1265		44.9	1297.4	0.0796	NA	-
3	972	513	445	0.0527	1630		43.9	1861.9	0.1172	NA	-
4	1139	509	617	0.0736	2295		43.7	2326.8	0.1470	0.166	88.6
5	1285	497	771	0.0937	2688		43.1	2719.5	0.1742	0.1962	86.8
6	1448	461	948	0.1154	2997		42.4	3026.1	0.1974	0.226	87.3
7	1467	297	1148	0.224	3113	19.9	52.2	3135.0	0.2756	0.267	96.1

H.P. L Calculated


$$H.P. P = 0.98 (H.P. TOT - H.P. L) \quad \eta_P = 0.96 \text{ Used in all predicted calculations}$$

BEST AVAILABLE COPY

FIGURE 4.1

LACV-30+1

ACCEPTANCE TEST - SPEED RUN OVER WATER



OUTPUT HORSE POWER ~ H.P.

$W_G = 76000$ LBS.
 $V_{wing} = 0.0$ MPH
 $P_{max} = 29.93$ 1.0 HP
 $TEMP = 37.4$ °F
 $N_2 = 95\%$

FIGURE 4.2

LACV-30-2

ACCEPTANCE TEST - SPEED RUN OVER WATER




FIGURE 4.3
LACV-30-1

TURNING RADIUS OVER WATER





FIGURE 4.4
LACV-30-1

TURNING RADIUS OVER WATER



APPENDIX A

CONTRACTORS' ACCEPTANCE TESTS

BELL AEROSPACE ACV TEST PLAN			TYPE LACV-30-2		OPER. NO. S2- 0410	
ACV CREW		NO CHASE AIRCRAFT		91,000 lb. TEST CONDITIONS		
CREW POSITION	NAME	TYPE A/C	CREW		TAKEOFF	LAND
Operator	G. Yeager			WEIGHT	91,000	89,000
Oper. NAV	R. Towers			FUEL	SEE Load. #2	
Inst.	E. Schiffmacher			C.G.	440'	
Engr.	R. Speth	INSTRUMENTATION PLAN		BALLAST		
		SETUP NO.	AMEND NO.	ALT SETTING	29.96	
		RADIO FREQ.		PRESS ALT	590'	
TEST ENGINEER	M. Laszewski	Not Required		WIND	020/20	
TEST DIRECTOR	M. Laszewski			TEMP	149°C ± 57°C	
FINAL GO-NO GO AUTHORITY	G. Yeager					
CRAFT CHANGES SINCE LAST OPERATION				TEST PURPOSE		
				I. Skirt pressure survey at 91,000 lb. G.W.		
				II. Cabin contamination sampling.		
TEST ENGINEER Signed		OPER. IN COMMAND Signed		APPROVAL		
TEST PROCEDURE						
Position craft on selected concrete ramp. Perform standard checklists. Tether craft at stern.						
I. Conduct skirt pressure survey in accordance with Attachment I (M. Laszewski's IOM).						
II. During the above test, sample cabin atmosphere at breathing level for noxious and toxic fumes using sampling kit provided by Safety Engineering. Record data on Attachment II.						

CABIN CONTAMINATION
(Tethered - Max. Power)

A. Craft Configuration:

T ₇ (°C)	<u>490</u>	<u>480</u>	<u>460</u>	<u>440</u>
N ₁ (%)	<u>98.2</u>	<u>98.5</u>	<u>98.3</u>	<u>96.0</u>
N ₂ (%)	<u>95</u>	<u>95</u>	<u>95</u>	<u>95</u>
TOP (psi)	<u>27</u>	<u>27</u>	<u>25</u>	<u>25</u>
Air Conditioner	<u>OFF</u>			
Heater	<u>OFF</u>			
Cabin Vents	<u>CLOSED</u>			

B. Environment:

OAT (°C)	<u>+47°C</u>	Baro. (in. Hg)	<u>29.32</u>
Wind Direction	<u>050°</u>	Craft Heading	<u>230°</u>
Wind Velocity	<u>30 mph</u>		

C. Samples:

<u>Fumes</u>	<u>Measured (ppm)</u>	<u>Limit (ppm)</u>
<u>Carbon Monoxide</u>	<u>50</u>	<u>50</u>
<u>Carbon Dioxide</u>	<u>5500</u>	<u>5000</u>
<u>Nitrogen Dioxide</u>	<u>unmeasurable</u>	<u>5</u>
<u>Sulfur Dioxide</u>	<u>unmeasurable</u>	<u>5</u>
<u>Unburned Hydrocarbons</u>	<u>50</u>	<u>Various</u>
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____
_____	_____	_____

BEST AVAILABLE COPY

OBSERVATIONS:

Spent the day in the field
at the [illegible] (C. [illegible])
at [illegible]. [illegible]
by [illegible] [illegible]

BEST AVAILABLE COPY

AD-A053 610


BELL AEROSPACE TEXTRON BUFFALO N Y
LACV-30 TEST AND DEMONSTRATION REPORT.(U)
FEB 78 M M LASZEWSKI
7467-928009

F/G 1/3

UNCLASSIFIED

DAAK02-75-C-0149
NL

2 OF 2
ADA
063610



END
DATE
FILMED
6-78
DDC

BELL AEROSPACE ACV TEST PLAN			TYPE LACV-30-2		OPER. NO. S2-0410	
ACV CREW		NO CHASE AIRCRAFT		91,000 lb. TEST CONDITIONS		
CREW POSITION	NAME	TYPE A/C	CREW		TAKEOFF	LAND
Operator	G. Yeager			WEIGHT		
Oper. NAV	R. Towers			FUEL		
Inst.	E. Schiffmacher			C.G.		
Engr.	R. Speth	INSTRUMENTATION PLAN		BALLAST		
		SETUP NO.	AMEND NO.	ALT SETTING		
		RADIO FREQ.		PRESS ALT		
TEST ENGINEER	M. Laszewski	Not Required		WIND		
TEST DIRECTOR	M. Laszewski			TEMP		
FINAL GO NO GO AUTHORITY	G. Yeager					
CRAFT CHANGES SINCE LAST OPERATION				TEST PURPOSE		
				I. Skirt pressure survey at 91,000 lb. G.W. II. Cabin contamination sampling.		
TEST ENGINEER Signed		OPER. IN COMMAND Signed		APPROVAL		
TEST PROCEDURE						
Position craft on selected concrete ramp. Perform standard checklists. Tether craft at stern. I. Conduct skirt pressure survey in accordance with Attachment I (M. Laszewski's IOM). II. During the above test, sample cabin atmosphere at breathing level for noxious and toxic fumes using sampling kit provided by Safety Engineering. Record data on Attachment II.						
Copied DATA - Informally sent to J. Sargent. C. Stauff 7/1/76						

CABIN CONTAMINATION
(Tethered - Max. Power)

A. Craft Configuration:

T ₅ (°C)	<u>440</u>	<u>480</u>	<u>460</u>	<u>440</u>
N ₁ (%)	<u>98.2</u>	<u>98.5</u>	<u>98.3</u>	<u>96.0</u>
N ₂ (%)	<u>95</u>	<u>95</u>	<u>95</u>	<u>95.5</u>
TOP (psi)	<u>27</u>	<u>27</u>	<u>25</u>	<u>25</u>
Air Conditioner	<u>OFF</u>			
Heater	<u>ON *</u>			
Cabin Vents	<u>CLOSED</u>			

B. Environment:

OAT (°C)	<u>+9°C</u>	Baro. (in. Hg)	<u>29.96</u>
Wind Direction	<u>195°</u>	Craft Heading	<u>210°</u>
Wind Velocity	<u>30 mph.</u>		

C. Samples:

<u>Fumes</u>	<u>Measured (ppm)</u>	<u>Limit (ppm)</u>
<u>Carbon Monoxide</u>	<u>30-40</u>	<u>100</u>
<u>Carbon Dioxide</u>	<u>3500</u>	<u>5000</u>
<u>Sulfur Dioxide</u>	<u>2-3</u>	<u>5</u>
<u>Nitrogen Dioxide</u>	<u>0</u>	<u>5</u>
<u>BENZENE</u>	<u>0</u>	<u>10</u>
<u>Chlorine</u>	<u>Trace to 80</u>	<u>200</u>
<u> </u>	<u> </u>	<u> </u>
<u> </u>	<u> </u>	<u> </u>
<u> </u>	<u> </u>	<u> </u>
<u> </u>	<u> </u>	<u> </u>

* One heater LO A-6

OBSERVATIONS:

This WAS A repeat Test. Previous measurements showed similar but incomplete Func DATA.

Note That Tests for Aldehydes WAS reactive, not definitive; i.e., did not define the Types present.



WIRE ROPE CORPORATION OF AMERICA, INC.

Fabricated Products Division

609 North 2nd Street • P. O. Box 288 • Saint Joseph, Missouri 64502 • 816/233-0287 • Telex 42546

September 19, 1975

CERTIFICATION OF PROOF TEST

To Whom It May Concern:

This is to certify that the 22 ton capacity adjust-a-leg wire rope assembly sold and shipped to The Caldwell Company Incorporated of Rockford, Illinois on their purchase order number 10353, file number 43753, have been proof tested to 84,000 pounds with legs vertical.

WIRE ROPE CORP. OF AMERICA, INC.

A handwritten signature in cursive script, appearing to read "D. Giannattasio".

D. Giannattasio, Manager
Fabricated Products

DG:sb

Subscribed And Sworn To Before Me

This 19th Day Of September, 1975

A handwritten signature in cursive script, appearing to read "R. L. ...".

Notary Public

My Commission Expires March 7, 1979

APPENDIX B

1976 IR&D REPORT 7467-928002 "COMPARISON OF
MEASURED AND PREDICTED HOVER PERFORMANCE OF
LACV-30 VEHICLES AT BATNFO" 31 DECEMBER 1976

Bell Aerospace **TEXTRON**

Division of Textron Inc.

Post Office Box One
Buffalo, New York 14240
716/297-1000

1976 IR&D FINAL REPORT

COMPARISON OF MEASURED AND PREDICTED HOVER
PERFORMANCE OF LACV-30 VEHICLES AT BATNFO

PROJECT NO. 21508

REPORT NO. 7467-928022

31 DECEMBER 1976

PRINCIPAL INVESTIGATOR: M. LASZEWSKI

TABLE OF CONTENTS

	<u>PAGE</u>
I. INTRODUCTION	1
II. SUMMARY	2
III. TEST PROGRAM AND VEHICLES	3
IV. INSTRUMENTATION	5
V. DATA REDUCTION	7
VI. DISCUSSION OF RESULTS	8
VII. SUMMARY OF RESULTS	12
VIII. RECOMMENDATIONS	13
IX. REFERENCES	14

LIST OF SYMBOLS

AG	Air Gap - in. or ft.
B _C	Cushion beam - ft.
EAG	Equivalent Air Gap - in. or ft.
F	Froude No. $\frac{V}{\sqrt{gL_C}}$
g	Acceleration due to gravity - ft/sec ²
H.H.	Heave height - in.
H.P.	Horsepower
L _C	Cushion length - ft.
N _F	Lift Fan Speed - RPM
P _B	Peripheral bag pressure - PSF
P _{AB}	Anti-bounce bag pressure - PSF
P _C	Cushion pressure - PSF
Q	Flow rate - CFS
S _C	Cushion area - ft ²
W _G	Gross weight - lbs.
δ	Ratio of test barometric pressure to standard day sea level pressure (29.92 in.Hg)
θ	Ratio of test temperature to standard day temperature (59°F)

LIST OF TABLES

<u>TABLE NO.</u>		<u>PAGE</u>
I	LACV-30-1 TEST WEIGHT - TEST NO. 2	15
II	LACV-30-1 TEST WEIGHT - TEST NO. 3	16
III	LACV-30-2 TEST WEIGHT - TEST NO. 1	17
IV	STATIC TEST SUMMARY	18
V	VOYAGEUR 002 STATIC TEST JUNE 1972	29

LIST OF FIGURES

<u>FIGURE NO.</u>		<u>PAGE</u>
1	3 VIEW AND GENERAL ARRANGEMENT - LACV-30	30
2	STARBOARD VIEW OF LACV-30-1 ON HANGAR RAMP, $W_G = 92,000$ LBS.	31
3	THREE-QUARTER VIEW OF LACV-30-1 ON HANGAR RAMP, $W_G = 92,000$ LBS.	32
4	STERN VIEW OF LACV-30-1 ON HANGAR RAMP, $W_G = 92,000$ LBS.	33
5	PORT VIEW OF LACV-30-2 VEHICLE ON CONCRETE RAMP, $W_G = 92,000$ LBS., $N_2 = 90\%$	34
6	STARBOARD VIEW OF LACV-30-2 VEHICLE ON CONCRETE RAMP, $W_G = 92,000$ LBS., $N_2 = 90\%$	35
7	STERN VIEW OF LACV-30-2 VEHICLE SHOWING MODIFIED STERN SEAL, $W_G = 92,000$ LBS., $N_2 = 90\%$	36
8	WEDGE USED TO MEASURE CUSHION AIR GAP	37
9	LACV-30 FLIGHT TEST RESULTS, CUSHION AREA, ALL TEST GROSS WEIGHTS	38
10	LACV-30-1 FLIGHT TEST RESULTS AVERAGE PERIPHERAL BAG PRESSURE $W/\delta = 94,302$ LBS.	39
11	LACV-30-2 FLIGHT TEST RESULTS AVERAGE PERIPHERAL BAG PRESSURE $W_G/\delta = 116,000$ LBS.	40
12	LACV-30-2 FLIGHT TEST RESULTS AVERAGE PERIPHERAL BAG PRESSURE $W/\delta = 93,820$ LBS.	41
13	LACV-30-1 FLIGHT TEST RESULTS AFT PERIPHERAL BAG PRESSURE $W/\delta = 94,302$ LBS.	42
14	LACV-30-1 FLIGHT TEST RESULTS AFT PERIPHERAL BAG PRESSURE $W_G/\delta = 116,000$ LBS.	43

LIST OF FIGURES (Cont'd)

<u>FIGURE NO.</u>		<u>PAGE</u>
15	LACV-30-2 FLIGHT TEST RESULTS AFT PERIPHERAL BAG PRESSURE $W/\delta = 93,820$ LBS.	44
16	LACV-30-1 FLIGHT TEST RESULTS AIR GAP VARIATION WITH FAN SPEED $W_G/\delta = 116,000$ LBS.	45
17	LACV-30-2 FLIGHT TEST RESULTS AIR GAP VARIATION WITH FAN SPEED $W/\delta = 93,820$ LBS.	46
18	LACV-30-1 FLIGHT TEST RESULTS HEAVE HEIGHT VARIATION WITH FAN SPEED, $W_G/\delta = 94,302$ LBS.	47
19	LACV-30-1 FLIGHT TEST RESULTS HEAVE HEIGHT VARIATION WITH FAN SPEED, $W_G/\delta = 116,000$ LBS.	48
20	LACV-30-2 FLIGHT TEST RESULTS HEAVE HEIGHT VARIATION WITH FAN SPEED, $W/\delta = 93,820$ LBS.	49
21	LACV-30 TOTAL PREDICTED LIFT FAN FLOW RATE VARIATION WITH LIFT FAN SPEED AND GROSS WEIGHT	50
22	LACV-30 PREDICTED SIDE BAG PRESSURE VARIATION WITH LIFT FAN SPEED AND GROSS WEIGHT	51
23	LACV-30 PREDICTED BAG-TO-CUSHION PRESSURE RATIO VARIATION WITH LIFT FAN SPEED AND GROSS WEIGHT	52
24	LACV-30 PREDICTED EQUIVALENT AIR GAP (EAG) VARIATION WITH LIFT FAN SPEED AND GROSS WEIGHT	53
25	LACV-30 TOTAL PREDICTED LIFT FAN HORSEPOWER VARIATION WITH LIFT FAN SPEED AND GROSS WEIGHT	54

I. INTRODUCTION

The purpose of the hover tests on the LACV-30-1 and LACV-30-2 vehicles was to obtain trunk and cushion characteristics for a number of gross weights and lift fan speeds for comparison to test data obtained from the Stretched Voyageur Model Tests. The comparison of full scale to model would be used to evaluate the accuracy of model data if necessary to obtain test scale factors for future model tests of comparable configurations.

This report includes a description of both vehicles, test instrumentation and data reduction techniques. Results are presented and compared to calculated values obtained from a computer program which uses model test data as the basis for lift system performance.

II. SUMMARY

The purpose of the 1976 IR&D program was to perform full scale craft tests, evaluate the test results and correlate them with model test data. The initial task in the program was to perform hover tests of the full scale LACV-30-1 and LACV-30-2 vehicles at the Bell Aerospace Flight Test Facility in Wheatfield, New York.

The most extensive testing was performed on the LACV-30-1 where data was obtained for corrected gross weights of 83,678, 94,302 and 116,000 pounds. The lift fan speeds tested ranged from 930 to 980 RPM. All test data were corrected to standard day conditions for correlation and comparison. Instrumentation problems voided the test results obtained from the 83,678 pound gross weight condition. The LACV-30-2 test was performed for a corrected gross weight of 93,820 pounds and corrected lift fan speeds of 845, 907 and 955 RPM.

Analysis of the full scale test results indicate that the LACV-30 has a larger than predicted cushion footprint area with a corresponding reduction in cushion pressure.

The peripheral bag pressures measured in the tests were compared to predicted values obtained from a computer model of the lift system. The increased cushion area was used to calculate the predicted values. The use of immediate side deck pressure adjacent to the lift fan discharge area provided the best correlation to predicted values. A complete set of updated lift system performance predictions based upon the measured cushion area is included in this report.

The LACV-30 vehicle exhibited the same characteristic drop in bow bag pressure as seen on the Voyageur (002) craft; however, it appears that the addition of the stretch section resulted in a larger pressure drop from stern to bow bag pressure. The results of the 1/7.5 stretched Voyageur model tests indicated a negligible difference in peripheral bag pressure.

It is recommended that a continual monitoring of full scale data from the LACV-30 and Voyageur Vehicles be performed and the results incorporated into the computer lift system model for future design considerations.

III. TEST PROGRAM AND VEHICLES

The hover flight test program performed at Bell Aerospace in Wheatfield, New York, involved the use of two test vehicles, the LACV-30-1 and the LACV-30-2. The two vehicles are similar to the configuration shown in Figure 1. The configurations tested included volutes in both lift fan plenums, modified stern seal and surf fence. The volutes and new stern seal installations were the outgrowth of the Stretched Voyageur Model test program performed in the ACV Laboratory at Wheatfield, New York. The LACV-30-1 vehicle had a swing crane mounted on the bow as shown in Figure 1.

The LACV-30-1 vehicle was tested in January and February of 1976 at three gross weights; 82,000, 92,000 and 116,000 pounds. Instrumentation problems, described in the next section, voided the results of the 82,000 pound test gross weight. However, the unusually large movement of ballast fuel required to keep the craft in level trim was noted at that weight and resulted in a change in the test program. In the light weight condition the vehicle was tested in only one position on the hangar apron; facing south. In order to investigate the ballast trim effect it was recommended in future tests to rotate the vehicle 180 degrees to establish whether the uneven ground plane or the vehicle itself necessitated ballast fuel trim adjustment.

The second gross weight tested was 92,000 pounds. The test weight was obtained by increasing the fuel on board and increasing the ballast weight in the MILVAN mounted on the deck. A weight breakdown is presented in Table I. Figures 2, 3 and 4 are photographs of the test configuration. Four tests were performed, two lift fan speeds at each of the two vehicle positions, facing south and north. After the test, a survey of the test site or cushion footprint area was made to determine the slope of the apron surface. The northern area of the test site was found to be level. This area is covered by the forward cushion compartments of the vehicle when the vehicle is pointed north and covered by the aft cushion compartments when the vehicle is pointed south. The slope at the southern end of the test site was higher, varying in angle from 1 to 3 degrees. Changes in ground slope will cause vehicle movement due to varying air gap, a shifting of ballast fuel to trim the craft in an attempt to keep it level would be required to minimize fore and aft movement.

The final test of the LACV-30-1 was to have been performed at the design gross weight of 115,000 pounds. However, 1000 pounds of additional fuel was put into the tanks for a final gross weight of 116,000 pounds. A weight breakdown for the test configuration is presented in Table II. The procedure was the same as in the previous test performed at 92,000 pounds, two lift fan speeds for each vehicle position on the apron.

The LACV-30-2 vehicle was tested in April 1976. The test site was changed to a concrete ramp between the Chemistry Building and the runway approach area. The concrete ramp was surveyed to determine the best area for the test.

The test program was limited to one gross weight, 92,000 pounds, and three lift fan speeds for one vehicle position, due to the limited availability of the vehicle. The weight breakdown for the test is presented in Table III. Photographs of the vehicle are presented in Figures 5, 6 and 7.

IV. INSTRUMENTATION

All instrumentation was simple and direct visual readings were taken by the test engineer. The visual readings were recorded directly into data sheets for each specific run.

The intent of the program was to measure cushion pressures, bag and anti-bounce bag pressures and heave heights throughout the entire trunk system. The pressures were measured using an open ended tube which was inserted into the cushion and bag areas. The measuring stations are indicated in Table IV. The open ended probe was used in areas where low velocities were predicted and where dynamic pressures were expected to be negligible. These pressure readings represent both local total and static pressure.

In the first test of the LACV-30-1 at a gross weight of 82,000 pounds, Magnehelic gages were used to determine the pressures. Upon completion of the test the gages were returned to the Instrumentation Laboratory where it was discovered that the zero reading on all the gages had drifted significantly. The gages were reset to zero before a calibration could be made to correct the measured test data. No attempt was made to analyze the data for inclusion in this report.

The pressure readings in the remaining tests were read with a hand held pressure probe attached to a U-Tube manometer containing King indicating liquid. Corrections due to test temperature conditions were provided for data analysis by the instrumentation personnel.

Metal rods located at four corners of the vehicle were installed to provide deck heave height readings. Readings were taken with the craft resting on the landing pads in the power off condition and after trunk inflation at the specified lift fan speed. The intent of the heave height measurement was to determine cushion height and air gap height.

After two tests of the LACV-30-1 vehicle, gross weights of 82,000 and 92,000 pounds, it was felt that heave height measurements alone could not be used to determine air gap height. A calibrated wedge was used in the remaining tests to measure the gap between the bottom of the fingers and the ground. The wedge is shown in Figure 8. The gap measurements were read at stations 220 and 695 for both port and starboard sides of the craft. The stations are shown in Table IV.

It also became evident after the first two tests of the LACV-30-1 vehicle that the cushion area of the vehicle is larger than predicted. A cushion footprint of the LACV-30-1 vehicle at a gross weight of 116,000 pounds was obtained using chalk to outline the cushion. A cushion footprint was obtained for all three lift fan speeds during the LACV-30-2 tests.

Outside air temperature and barometric pressure were recorded on the data sheets. These data were used for normalizing test data to standard day conditions.

V. DATA REDUCTION

The bag and cushion pressure data were reduced by correcting the manometer readings for the test temperature and applying the proper conversion from inches of water to pounds per square foot. The two stern heave height readings were increased by 0.7 inches to account for the difference in deck height between the bow and stern measuring locations. The step decrease in deck height occurs at station 624.

The reduced data for each of the eleven tests are presented in Tables IVa through IVk. The data shown includes, P_B , bag pressure, P_{AB} , anti-bounce bag pressure, P_C , cushion pressure and AG, measured air gap.

For analysis the reduced data was corrected to standard day conditions, in the following form:

$$\text{Bag Pressure} \sim P_B/\delta \sim \text{PSF}$$

$$\text{Lift Fan Speed} \sim N_F/\sqrt{\theta} \sim \text{RPM}$$

$$\text{Cushion Pressure} \sim P_C/\delta \sim \text{RPM}$$

$$\text{Bag-to-Cushion pressure ratio} \sim P_B/P_C$$

$$\text{Gross Weight} \sim W_G/\delta \sim \text{LBS.}$$

$$\text{Heave Height} \sim \text{H.H.} \sim \text{inches}$$

$$\text{Air Gap Height} \sim \text{AG} \sim \text{FT}$$

The predicted hover characteristics include the following items:

$$\text{Horsepower} \sim \frac{\text{H.P.}}{\delta \sqrt{\theta}}$$

$$\text{Cushion Flow} \sim \frac{Q}{\sqrt{\theta}} \sim \text{CFS}$$

θ is the ratio of test temperature to standard day temperature of 518.9° Rankine and δ is the ratio of test barometric pressure to standard day barometric pressure of 29.92 inches of mercury.

VI. DISCUSSION OF RESULTS

The purpose of the hover flight tests on the LACV-30 full scale vehicle was to obtain trunk characteristics for comparison to predicted values obtained from a computer program. The computer program was developed using Stretched Voyageur model test data for determination of lift system losses. The program titled, VOYLSV3, calculates the total system air flow and distribution of flow, equivalent air gap (EAG), power requirements and pressures throughout the system. Details of the entire program can be found in reference 2.

The Stretched Voyageur model test data indicated the difference in peripheral bag pressure from stern to bow to be negligible. Therefore the average of all trunk pressure was used to determine the lift system losses from lift fan plenum to the side deck or peripheral bag. The computer program calculates one peripheral bag pressure and assumes that both lift fans provide the same bag pressure and flow. The air gap, which is the cushion flow discharge area between the bottom of the fingers and the ground is calculated using the sum of cushion flow from the peripheral and stability bags. The stern bag flow is a separate calculation and is not included in the air gap calculation because it is assumed to exhaust to atmosphere. The program has the capability to account for loss of flow due to leakage area. Because the leakage area was set to zero for this study, the calculated air gap is actually the so-called "equivalent air gap."

The cushion pressure (P_C) is calculated directly from input vehicle weight and cushion geometry. Since it is a major parameter in the program, cushion geometry must be correctly established in order to obtain a valid comparison of full scale test results to predicted values.

Figure 9 presents the variation of effective and measured cushion areas as a function of lift fan speed. The effective cushion area is defined as the test gross weight divided by the average test cushion pressure. The measured cushion areas were obtained from actual footprints of the vehicle at four test conditions. The initial design assumption of cushion area as shown in Figure 9 was for a cushion length (L_C) of 67.2 feet and a cushion beam (B_C) of 31.3 feet. As can be seen in the figure the test results indicate that the LACV-30 has a larger cushion area than previously assumed. The measured footprints varied in length from 69.8 to 70.5 feet and in width from 32.5 to 33.5 feet. For comparison to test results, a cushion length of 70.5 feet and beam of 33.5 feet were used to calculate predicted performance. The resultant cushion area is indicated by a solid line in Figure 9 and appears to be a good average of all the test data shown.

The stretched Voyageur model data indicated that the average of all peripheral bag pressures could be used to calculate lift system performance. An attempt was made to correlate the computed values with test data by averaging the peripheral bag pressures for each full scale test. The LACV-30-1 results for the 92,000 gross weight (or a corrected weight of 94,302 pounds) are shown in Figure 10. The solid line is the calculated values of bag and cushion pressures using the model test pressure loss of 0.5 to account for loss in pressure between the lift fan plenum and side bag. The average test bag pressures show a considerable disagreement with the predicted values. To determine if this discrepancy could be due to a small change in the loss coefficient, the coefficient was arbitrarily increased until agreement was reached. As shown in Figure 10, the test data shows good agreement with the calculated values only when the anticipated pressure loss coefficient is increased by a factor of three.

The flight test results for the corrected gross weight of 116,000 pounds shown in Figure 11 exhibit the same characteristics as those obtained in the lighter weight test. Again, average peripheral bag pressure agrees with the calculated value only when the pressure loss coefficient is increased from 0.5 to 1.25.

The LACV-30-2 test results shown in Figure 12 for a corrected gross weight of 93,820 pounds exhibits the same characteristics as the test results shown in Figure 10. Based upon the results obtained from both vehicles it is quite apparent that the use of average bag pressure from the full scale craft does not correlate with the predicted values.

The pressure losses included in the computer program were obtained from 1/7.5 scale model tests where the peripheral bag pressure variation from stern to bow was negligible. The full scale test data shown in Table IV does not indicate the same trend. The test data indicates a decrease in bag pressure with increasing distance away from the lift fan discharge area. The pressure drop from stern to bow is approximately 15 percent. Of some concern is the stretched trunk system drop in bag-to-cushion pressure ratio at the bow and its relationship to plow-in tendencies.

The results of a trunk system pressure survey performed on the full scale Voyageur, craft 002, are presented in Table V. The data taken in June of 1972 indicates no significant change in bag pressure along the side deck. However, the bow bag pressure does drop an average of 7 percent for a majority of the tests. It can therefore be concluded that the addition of the stretch section resulted in a larger than expected pressure drop in the peripheral bag. This loss in pressure also makes it difficult to predict lift system performance using average peripheral bag pressures.

A more significant pressure that can be used for estimating lift system performance is the side bag pressure measured in the vicinity of the lift fan plenum discharge area. Here the pressure is only affected by the lift fan output and the obstructions in the discharge area and does not include losses which occur downstream of the fan discharge area.

Figures 13, 14 and 15 present flight test values obtained by averaging the most aft readings in the port and starboard peripheral bag sections. The center line of the 7 foot diameter lift fan is at station 740. The readings as shown in Table IV were taken at station 695 which is in the area of flow discharge to the side bag.

The predicted or computed values shown in the figures were calculated using the model test pressure loss coefficient of 0.5 to account for loss in pressure between lift fan plenum and side bag. The flight test results for the corrected weights of 94,302 pounds, 116,000 pounds and 93,820 pounds show good agreement with the calculated values of bag pressure. The correlation indicates that a modification should be made to the computer program to include a bow pressure calculation to account for downstream pressure losses and variation in total cushion flow.

The comparison of measured air gap and predicted values is presented in Figures 16 and 17 for corrected weights of 116,000 and 93,820 pounds. Only a limited amount of test data is available since air gap measurement using a calibrated wedge was introduced late in the test program. The computer program assumes level ground and uniform flow exiting from the bottom of the fingers with no leakage between fingers or corners of the trunk system. In reality the ground at the test site is uneven and efforts to keep the craft level resulted in variable exit flow areas around the periphery of the cushion.

The data shown in Figures 16 and 17 are the average of the gap measurements taken during the tests. Their general agreement with predicted values demonstrate satisfactory lift system performance.

Heave height measurements, the distance from ground to deck, are presented in Figures 18, 19 and 20 for corrected cross weights of 94,302 pounds, 116,000 pounds and 93,820 pounds. The predicted value was calculated using the sum of the predicted air gap, theoretical cushion height of 47.5 inches and deck height of 37.5 inches. The heave height reading for the no-gap condition should be 85.0 inches. All the test data shown in the three figures show a divergent trend with the predicted with decreasing lift fan speed. Factors which influence heave height readings are uneven ground at the test site and variation of peripheral bag shape with bag-to-cushion pressure ratio. The measured air gap is a better indication of lift system performance.

The test results can be considered to have validated the computer program, provided that the side bag pressure adjacent to the lift fan discharge area is used for bag pressure and an increased cushion area (2315 ft^2) is used. For future prediction purposes, the calculated lift system performance over the range of vehicle weights from 70,000 to 120,000 pounds and lift fan speeds from 695 to 1000 RPM are presented in Figures 21 through 25 as part of this report. The predicted performance includes total cushion flow ($Q/\sqrt{\theta}$), side bag pressure (P_B/δ), bag-to-cushion pressure ratio, air gap (AG) and total required horsepower ($\text{H.P.}/\delta\sqrt{\theta}$).

VII. SUMMARY OF RESULTS

1. The full scale tests indicated a larger than predicted cushion footprint area with a corresponding reduction in cushion pressure.

2. The average peripheral bag pressure did not correlate with predicted values of bag pressure obtained from a lift system computer program.

3. Correlation of peripheral bag pressure with predicted values was obtained using the average of port and starboard side bag pressures measured adjacent to the lift fan discharge area.

4. The air gap measurement using the calibrated wedge was more indicative of lift system performances than the measured heave height at the deck level. The measured air gap heights were comparable to the predicted.

5. The LACV-30 exhibited the same characteristic drop in bow bag pressure as seen on the Voyageur (002) craft; however, it appears **that** the addition of the stretch section resulted in a larger decrease in bag pressure with increasing distance away from the lift fan discharge area.

VIII. RECOMMENDATIONS

The full scale test data indicated a 15 percent pressure drop from stern to bow in the peripheral bag. Stretched Voyageur model test data, which is the basis for predicting lift system performance, indicated the difference in peripheral bag pressure from stern to bow to be negligible.

The discrepancy in trunk system characteristics must be resolved in order to establish prediction techniques where vehicle growth is obtained by stretching the existing seal system.

The following recommendations are being made to improve our design capability:

1. A continual monitoring of static bag pressure data from full scale craft such as the LACV-30 and Voyageur.
2. Incorporation of the full scale data into the computer program to include bow bag pressure calculations accounting for downstream losses and variations in total flow.
3. An attempt should be made using the stretch Voyageur model to determine model to full scale relationship with regards to bag shape and pressure distribution and establish areas of discrepancies.

IX. REFERENCES

1. Laszewski, M. & Watt, C. S., "Stretched Voyageur Model Testing," Bell Aerospace, Report No. 7467-927001, 31 December 1974.
2. Bissell, J. R., "VOYLSV3 - A Digital Computer Program for Evaluating ACV Type Lift/Seal System Performance," Bell Aerospace, Report No. 7467-927013, May 1976.

TABLE I
LACV-30-1 TEST WEIGHT

TEST NO. 2

BASIC CONFIGURATION 58,072 LBS.

LASHINGS	475
AFT PALLET	945
PALLET TIE BAR	85
MILVAN	4745
CREW	360
PASSENGER	360
UNUSEABLE FUEL	<u>650</u>

7620 LBS.

OPERATING WEIGHT EMPTY 65,692 LBS

FUEL 12,583 LBS.

BALLAST 13,725 LBS.

FLIGHT CONDITION 92,000 LBS.

TABLE II
LACV-30-1 TEST WEIGHT
TEST NO. 3

BASIC CONFIGURATION	58,240 LBS.
LASHINGS	950
PALLETS	2008
PALLET TIE BARS	170
MILVANS (2)	9345
CREW	360
PASSENGERS	360
UNUSEABLE FUEL	<u>650</u>
	13,843 LBS.
OPERATING WEIGHT EMPTY	72,083 LBS.
FUEL	18,546 LBS.
BALLAST	25,371
FLIGHT CONDITION	116,000 LBS.

TABLE III
LACV-30-2 TEST WEIGHT
TEST NO. 1

BASIC CONFIGURATION	51,859 LBS.
LASHING	428
PALLET	2064
PALLET TIE BAR	170
MILVAN	4745
CREW	360
PASSENGERS	360
UNUSEABLE FUEL	650
TEE HOOKS	<u>152</u>
	8929 LBS.
OPERATING WEIGHT EMPTY	60,788 LBS.
FUEL	16,881 LBS.
BALLAST	14,331 LBS.
FLIGHT CONDITION	92,000 LBS.

VEHICLE LACV-30-1 Facing North (1)

TIME 10:00 a.m.

OAT/BARO 21°F/29.17

DATE: 1/30/76

WEIGHT 92,000 lbs.

WIND _____

N₂ 91%

FAN RPM 905

P_{AB} 60.5 psf
(B.L. 86)

P_{AB} 60.0 psf
(B.L. 86)

P_B 60.5 psf
(B.L. 54.5)

B.L. 54.5 in. B.L. 54.5 in.

P_B 60.5 psf
(B.L. 54.5)




TABLE IV_a

STATIC TEST RUN SUMMARY

VEHICLE LACV-30-1 Facing North (2)

TIME 11:00 a.m.

OAT/BARO 21°F/29.17

DATE: 1/30/76

WEIGHT 92,000 lbs.

WIND _____

N₂ 93.5%

FAN RPM 930

P_{AB} 64.2 psf
(B.L. 86)

P_{AB} 64.2 psf
(B.L. 86)

P_B 64.8 psf
(B.L. 54.5)

B.L. 54.5 in. B.L. 54.5 in.

P_B 64.2 psf
(B.L. 54.5)




TABLE IV b

STATIC TEST RUN SUMMARY

VEHICLE LACV-30-1 Facing South (3)

TIME 2:30 p.m.

OAT/BARO 23°F/29.17

DATE: 1/30/76

WEIGHT 92,000 lbs.

WIND _____

N₂ 91%

FAN RPM 905

P_{AB} 58.3 psf
(B.L. 86)

P_{AB} 58.3 psf
(B.L. 86)

P_B 57.8 psf
(B.L. 54.5)

B.L. 54.5 in. B.L. 54.5 in.

P_B 58.3 psf
(B.L. 54.5)




TABLE IVc

STATIC TEST RUN SUMMARY

VEHICLE LACV-30-1 Facing South (4)

TIME 3:30 p.m. OAT/BARO 23°F/29.17 DATE: 1/30/76

WEIGHT 92,000 lbs. WIND _____

N₂ 95.8% FAN RPM 953

P_{AB} 61.5 psf
(B.L. 86)

P_{AB} 61.5 psf
(B.L. 86)

P_B 61.5 psf
(B.L. 54.5)

B.L. 54.5 in. B.L. 54.5 in.

P_B 61.5 psf
(B.L. 54.5)




TABLE IV d

STATIC TEST RUN SUMMARY

VEHICLE LACV-30-1 Facing South (1)

TIME 11:00 a.m.

OAT/BARO 32°F/29.93

DATE: 2/14/76

WEIGHT 116,000 lbs

WIND _____

N₂ 91%

FAN RPM 905

P_{AB} 66.0 psf
(B.L. 86)

P_{AB} 66.0 psf
(B.L. 86)

P_B 66.0 psf
(B.L. 54.5)

B.L. 54.5 in. B.L. 54.5 in.

P_B 66.0 psf
(B.L. 54.5)




TABLE IV e

STATIC TEST RUN SUMMARY

VEHICLE LACV-30-1 Facing South (2)

TIME 11:20 a.m. OAT/BARO 32°F/29.93 DATE: 2/14/76

WEIGHT 116,000 lbs. WIND 8 mph 320 deg.

N₂ 95% FAN RPM 945

P_{AB} 70.3 psf
(B.L. 86)

P_{AB} 70.3 psf
(B.L. 86)

P_B 70.3 psf
(B.L. 54.5)

B.L. 54.5 in. B.L. 54.5 in.

P_B 70.8 psf
(B.L. 54.5)




TABLE IV_f

STATIC TEST RUN SUMMARY

VEHICLE LACV-30-1 Facing North (3)

TIME 1:34 p.m.

OAT/BARO 32°F/29.93

DATE: 2/14/76

WEIGHT 116,000 lbs

WIND

N₂ 91%

FAN RPM 905

P_{AB} 67.1 psf
(B.L. 86)

P_{AB} 67.1 psf
(B.L. 86)

P_B 67.1 psf
(B.L. 54.5)

B.L. 54.5 in.

B.L. 54.5 in.

P_B 66.6 psf
(B.L. 54.5)




TABLE IVg

STATIC TEST RUN SUMMARY

VEHICLE LACV-30-1 Facing North (4)

TIME 2:00 p.m.

OAT/BARO 32°F/29.93

DATE: 2/14/76

WEIGHT 116,000 lbs.

WIND _____

N₂ 96.25%

FAN RPM 957

P_{AB} 72.4 psf
(B.L. 86)

P_{AB} 71.3 psf
(B.L. 86)

P_B 71.8 psf
(B.L. 54.5)

B.L. 54.5 in.

B.L. 54.5 in.

P_B 71.8 psf
(B.L. 54.5)




TABLE IV h

STATIC TEST RUN SUMMARY

VEHICLE LACV-30-2 on concrete ramp towards airport

TIME 1:00 p.m. OAT/BARO 49°F/29.32 DATE: 4/10/76

WEIGHT 92,000 lb. WIND _____

N₂ 95% FAN RPM 945

P_{AB} 59.8 psf
(B.L. 86)

P_{AB} 59.8 psf
(B.L. 86)

P_B 59.8 psf
(B.L. 54.5)

B.L. 54.5 in.
2.0 in.

B.L. 54.5 in.
1.75 in.

P_B 60.3 psf
(B.L. 54.5)




TABLE IV

STATIC TEST RUN SUMMARY

VEHICLE LACV-30-2 on concrete ramp towards airport

TIME 1:55 p.m. OAT/BARO 57°F/29.32 DATE: 4/10/76

WEIGHT 92,000 lbs. WIND _____

N₂ 90% FAN RPM 905

P_{AB} 54.9 psf
(B.L. 86)

P_{AB} 55.4 psf
(B.L. 86)

P_B 54.9 psf
(B.L. 54.5)

B.L. 54.5 in. B.L. 54.5 in.
1.0 in. 1.5 in.

P_B 54.9 psf
(B.L. 54.5)




TABLE IV j

STATIC TEST RUN SUMMARY

VEHICLE LACV-30-2 on concrete ramp towards airport

TIME 2:30 p.m. OAT/BARO 57°F/29.32 DATE: 4/10/76

WEIGHT 92,000 lbs. WIND _____

N₂ 85% FAN RPM _____

P_{AB} 51.2 psf
(B.L. 86)

P_{AB} 51.7 psf
(B.L. 86)

P_B 51.2 psf
(B.L. 54.5)

B.L. 54.5 in. B.L. 54.5 in.
0.625 in. 1.5 in.

P_B 51.2 psf
(B.L. 54.5)





TABLE IV k

STATIC TEST RUN SUMMARY

TABLE V

P1	CENTER KEEL PRESSURE
P2	PORT REAR TRUNK PRESSURE
P3	PORT AFT INNER PERIPHERAL TRUNK PRESSURE
P4	PORT AFT OUTER PERIPHERAL TRUNK PRESSURE
P5	CUSHION PRESSURE
P6	PORT STABILITY TRUNK PRESSURE
P7	PORT FORWARD OUTER PERIPHERAL TRUNK PRESSURE
P8	PORT FORWARD INNER PERIPHERAL TRUNK PRESSURE
P9	CUSHION PRESSURE
P10	DOW TRUNK PRESSURE
P11	STBD. REAR TRUNK PRESSURE
P12	STBD. AFT INNER PERIPHERAL TRUNK PRESSURE
P13	STBD. AFT OUTER PERIPHERAL TRUNK PRESSURE
P14	CUSHION PRESSURE
P15	STBD. STABILITY TRUNK PRESSURE
P16	STBD. FORWARD OUTER PERIPHERAL TRUNK PRESSURE
P17	STBD. FORWARD INNER PERIPHERAL TRUNK PRESSURE
P18	CUSHION PRESSURE



VOYAGEUR 002 STATIC TEST JUNE 1972

CRAFT WEIGHT (LB)	H ₂ (%)	T _{AMB} (°F)	P1	P2	P3	P4	P5	P6	P7	P8	P9	P10	P11	P12	P13	P14	P15	P16	P17	P18
45,000	90	65	60.3	62.9	54.6	58.7	24.0	53.1	59.3	55.1	26.6	51.5	68.1	56.7	59.8	26.5	53.1	59.8	56.7	38.1
49,600	90	49	61.1	63.7	55.9	61.1	31.2	54.1	59.8	57.2	31.2	53.3	67.6	54.6	62.4	31.2	54.1	64.4	57.2	31.2
64,000	90	55	65.0	70.2	59.8	65.0	34.8	59.8	65.0	62.4	39.0	62.4	72.8	62.0	65.0	33.0	59.8	66.0	60.0	39.0
78,000	90	65	66.6	70.2	65.0	66.6	42.0	62.4	66.3	64.4	45.5	60.9	71.5	61.1	67.6	42.6	62.4	65.0	65.0	45.5
78,000	90	80	65.0	65.0	59.8	62.4	41.6	65.0	62.4	61.1	46.8	57.2	70.2	61.1	63.7	44.2	65.0	63.7	62.4	46.8
88,000	90	80	67.6	64.0	65.5	65.5	46.8	64.0	67.6	65.5	51.0	62.9	74.9	64.5	68.6	49.4	55.0	69.7	60.0	52.0

1. 100' CONCRETE WALL
 2. 100' CONCRETE WALL
 3. 100' CONCRETE WALL
 4. 100' CONCRETE WALL
 5. 100' CONCRETE WALL
 6. 100' CONCRETE WALL
 7. 100' CONCRETE WALL
 8. 100' CONCRETE WALL
 9. 100' CONCRETE WALL
 10. 100' CONCRETE WALL
 11. 100' CONCRETE WALL
 12. 100' CONCRETE WALL
 13. 100' CONCRETE WALL
 14. 100' CONCRETE WALL
 15. 100' CONCRETE WALL
 16. 100' CONCRETE WALL
 17. 100' CONCRETE WALL
 18. 100' CONCRETE WALL
 19. 100' CONCRETE WALL
 20. 100' CONCRETE WALL
 21. 100' CONCRETE WALL
 22. 100' CONCRETE WALL
 23. 100' CONCRETE WALL
 24. 100' CONCRETE WALL
 25. 100' CONCRETE WALL
 26. 100' CONCRETE WALL
 27. 100' CONCRETE WALL
 28. 100' CONCRETE WALL
 29. 100' CONCRETE WALL
 30. 100' CONCRETE WALL
 31. 100' CONCRETE WALL
 32. 100' CONCRETE WALL
 33. 100' CONCRETE WALL
 34. 100' CONCRETE WALL
 35. 100' CONCRETE WALL
 36. 100' CONCRETE WALL
 37. 100' CONCRETE WALL
 38. 100' CONCRETE WALL
 39. 100' CONCRETE WALL
 40. 100' CONCRETE WALL
 41. 100' CONCRETE WALL
 42. 100' CONCRETE WALL
 43. 100' CONCRETE WALL
 44. 100' CONCRETE WALL
 45. 100' CONCRETE WALL
 46. 100' CONCRETE WALL
 47. 100' CONCRETE WALL
 48. 100' CONCRETE WALL
 49. 100' CONCRETE WALL
 50. 100' CONCRETE WALL
 51. 100' CONCRETE WALL
 52. 100' CONCRETE WALL
 53. 100' CONCRETE WALL
 54. 100' CONCRETE WALL
 55. 100' CONCRETE WALL
 56. 100' CONCRETE WALL
 57. 100' CONCRETE WALL
 58. 100' CONCRETE WALL
 59. 100' CONCRETE WALL
 60. 100' CONCRETE WALL
 61. 100' CONCRETE WALL
 62. 100' CONCRETE WALL
 63. 100' CONCRETE WALL
 64. 100' CONCRETE WALL
 65. 100' CONCRETE WALL
 66. 100' CONCRETE WALL
 67. 100' CONCRETE WALL
 68. 100' CONCRETE WALL
 69. 100' CONCRETE WALL
 70. 100' CONCRETE WALL
 71. 100' CONCRETE WALL
 72. 100' CONCRETE WALL
 73. 100' CONCRETE WALL
 74. 100' CONCRETE WALL
 75. 100' CONCRETE WALL
 76. 100' CONCRETE WALL
 77. 100' CONCRETE WALL
 78. 100' CONCRETE WALL
 79. 100' CONCRETE WALL
 80. 100' CONCRETE WALL
 81. 100' CONCRETE WALL
 82. 100' CONCRETE WALL
 83. 100' CONCRETE WALL
 84. 100' CONCRETE WALL
 85. 100' CONCRETE WALL
 86. 100' CONCRETE WALL
 87. 100' CONCRETE WALL
 88. 100' CONCRETE WALL
 89. 100' CONCRETE WALL
 90. 100' CONCRETE WALL
 91. 100' CONCRETE WALL
 92. 100' CONCRETE WALL
 93. 100' CONCRETE WALL
 94. 100' CONCRETE WALL
 95. 100' CONCRETE WALL
 96. 100' CONCRETE WALL
 97. 100' CONCRETE WALL
 98. 100' CONCRETE WALL
 99. 100' CONCRETE WALL
 100. 100' CONCRETE WALL




FIGURE 1. 3 VIEW AND GENERAL ARRANGEMENT - LACV-30




FIGURE 2. STARBOARD VIEW OF LCV-30-1 ON BARGE RAIP, $M_0 = 92,000$ LBS.

BEST AVAILABLE COPY




FIGURE 1. THREE QUARTER VIEW OF LST-1041 ON HUNTER RAMP, W₂ = 92,000 LBS.

BEST AVAILABLE COPY




FIGURE 4. SIDE VIEW OF LSTC-30-1 OF 10,000 TONS, $N_C = 91,000$ TONS.

BEST AVAILABLE COPY




FIGURE 5. POINT VIEW OF L.C. 30-2 VIEWING OF CONCRETE DAM.
 $N = 32,000$ E.S.S., $d_2 = 308$

BEST AVAILABLE COPY





FIGURE 6. STARBOARD VIEW OF LACV-30-2 VEHICLE ON CONCRETE RAMP,
 $W_C = 92,000$ LBS., $I_2 = 903$

BEST AVAILABLE COPY



1. E. T. GUNN, III OF LACV-30-2 VEHICLE BEHIND MODEL ITS OPEN SIDE.
T. = 92,000 LBS., N. = 309

BEST AVAILABLE COPY



FIGURE 5. WEDGE USED TO MEASURE CURSION AT COP

FIGURE 9

LACV-30

FLIGHT TEST RESULTS
CUSHION AREA
ALL TEST GROSS WEIGHTS

————— VALUE USED IN ANALYSIS

- LACV-30-1 } $S_{EFF} = \frac{WG}{C}$
 □ LACV-30-2 }
 ⊗ LACV-30-1 } MEASURED
 ⊗ LACV-30-2 }

EFFECTIVE CUSHION AREA - S_{EFF} - SQ. FT.

2500

2400

2320

2200

2100

2000

500

600

700

800

900


1000


----- DESIGN ASSUMPTION


LIFT PLAT SPEED - $N \sqrt{\frac{WG}{C}} + KFA$

46 1323

K-E 10 X 10 TO 1/4 INCH 7 X 10 INCHES
KEUFFEL & ESSER CO. MADE IN U.S.A.









46 1323


K-E 10 X 10 TO 12 INCH 7 X 10 INCHES
KEUFFEL & ESSER CO. MADE IN U.S.A.



46 1323

K-Σ 10 X 10 TO 11 INCH 7 X 10 INCHES
KEUFFEL & ESSER CO. MADE IN U.S.A.





46 1323

K&E 10 X 10 TO 2 1/2 INCH 7 X 10 INCHES
KEUFFEL & ESSER CO. MADE IN U.S.A.

FIGURE 16

LACV-30-1

FLIGHT TEST RESULTS

AIR GAP VARIATION WITH MAX SPEED

$$\frac{W_0}{S} = 116,000 \text{ LBS}$$





FIGURE 17

LACV-30-2
 FLIGHT TEST RESULTS
 AIR GAP VARIATION WITH FAN SPEED
 $W/G = 93820 \text{ LBS}$



46 1323

K&E 10 X 10 TO 15 INCH 7 X 10 INCHES
KEUFFEL & ESSER CO. MADE IN U.S.A.


FIGURE 18

LACV-30-1

FLIGHT TEST RESULTS

HEAVE HEIGHT VARIATION WITH FAN SPEED

$$\frac{WG}{S} = 94302 \text{ LBS}$$



46 1323

K&E 10 X 10 TO 1/2 INCH 7 X 10 INCHES
KEUFFEL & ESSER CO. MADE IN U.S.A.

FIGURE 19 LACV-30-1

FLIGHT TEST RESULTS

HEAVE HEIGHT VARIATION WITH FAN SPEED

$W_0 = 116000 \text{ LBS.}$

δ




FIGURE 20 LACV-30-2

FLIGHT TEST RESULTS

HEAVE HEIGHT VARIATION WITH FAN SPEED

$$W/S = 93820 \text{ LBS}$$




FIGURE 21


LACV-30

TOTAL PREDICTED LIFT FAN FLOW RATE VARIATION
WITH LIFT FAN SPEED AND GROSS WEIGHT

TOTAL PREDICTED LIFT FAN FLOW RATE: $\frac{Q}{10} = GFS$

$$L_c = 10.5 \text{ FT}$$

$$D_c = 33.5 \text{ FT}$$



$$\frac{WG}{8} \sim \text{GROSS WEIGHT} \sim 2.55 \times 10^{-3}$$


NOTE: TOTAL FLOW IS FOR
TWO LIFT FANS

FIGURE 22

LACV-30

PREDICTED SIDE BAG PRESSURE VARIATION WITH
LIFT FAN SPEED AND GROSS WEIGHT

$L_0 = 70.5$ FT
 $C_L = 33.5$ FT






FIGURE 24

LACV-30

PREDICTED EQUIVALENT AIR GAP (EAG) VARIATION
WITH LIFT FAN SPEED AND GROSS WEIGHT




FIGURE 25


LACV-30

TOTAL PREDICTED LIFT FAN HORSEPOWER VARIATION

WITH LIFT FAN SPEED AND GROSS WEIGHT

$$L_0 = 70.5 \text{ FT.}$$

$$P_0 = 33.5 \text{ AT.}$$



NOTE: TOTAL POWER IS FOR TWO LIFT FANS.

W_G ~ GROSS WEIGHT ~ LBS X 10⁻³